


AD-A109 754

D'APPOLONIA CONSULTING ENGINEERS INC PITTSBURGH PA F/G 13/13  
NATIONAL DAM SAFETY PROGRAM. NEWTOWN-HOFFMAN WATERSHED PROJECT---ETC(U)  
SEP 81 L D ANDERSEN DACW51-81-C-0011


NL.

UNCLASSIFIED

1-1  
PAGE 754



END  
DATE  
FILMED  
2-82  
DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

AD A109754

01 19 82 058

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report Newton Hoffman Creek No. 1 Dam Chemung River Basin, Chemung County, NY Inventory No. 547		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s)  LAWRENCE D. ANDERSEN		6. PERFORMING ORG. REPORT NUMBER  DACW51-81-C-0011
9. PERFORMING ORGANIZATION NAME AND ADDRESS D'Appolonia Consulting Engineers, Inc. 10 Duff Road Pittsburgh, PA 15235		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS Department of the Army 26 Federal Plaza New York District, CofE New York, New York 10287		12. REPORT DATE September 14, 1981
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		13. NUMBER OF PAGES
15. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; Distribution unlimited.		15. SECURITY CLASS. (of this report)  UNCLASSIFIED
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Newton Hoffman Creek No. 1 Dam Chemung River Basin Chemung County		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization.  Based on the evaluation of the existing conditions, the condition of the Newtown-Hoffman Creeks Watershed Project - Floodwater Retarding Dam Site 1 is considered to be good. The examination of documents and		

DD FORM 1 JAN 71 1001 EDITION OF NOV 65 OBSOLETE

visual observations did not reveal conditions which constitute a hazard to human life or property.

The spillway capacity was evaluated according to the recommended procedure and was found to pass the required spillway design flood of 100 percent of the Probable Maximum Flood (PMF). Therefore, the spillway capacity is rated as adequate.

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For  
NTIS GR&I  
DTIC TAB  
Unannounced  
Justification  
By  
Date

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
NEWTOWN-HOFFMAN CREEKS WATERSHED PROJECT -  
FLOODWATER RETARDING DAM SITE 1  
N.Y. 547  
DEC I.D. NO. 67A-3974  
CHEMUNG RIVER BASIN  
CHEMUNG COUNTY, NEW YORK

TABLE OF CONTENTS

	<u>PAGE NO.</u>
ASSESSMENT	iv
OVERVIEW PHOTOGRAPH	vi
SECTION 1: PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
SECTION 2: ENGINEERING DATA	5
2.1 DATA AVAILABLE	5
2.2 GEOLOGY	5
2.3 SUBSURFACE INVESTIGATION	5
2.4 EMBANKMENT AND APPURTENANT STRUCTURES	6
2.5 CONSTRUCTION RECORDS	6
2.6 OPERATING RECORDS	6
2.7 EVALUATION OF DATA	6
SECTION 3: VISUAL INSPECTION	7
3.1 FINDINGS	7
3.2 EVALUATION	7
SECTION 4: OPERATION AND MAINTENANCE PROCEDURES	8
4.1 PROCEDURES	8

TABLE OF CONTENTS  
(Continued)

	<u>PAGE NO.</u>
4.2 MAINTENANCE OF THE DAM	8
4.3 WARNING SYSTEM IN EFFECT	8
4.4 EVALUATION	8
SECTION 5: HYDRAULIC/HYDROLOGY	9
5.1 DRAINAGE AREA CHARACTERISTICS	9
5.2 ANALYSIS CRITERIA	9
5.3 SPILLWAY CAPACITY	9
5.4 RESERVOIR CAPACITY	9
5.5 FLOODS OF RECORD	9
5.6 OVERTOPPING POTENTIAL	9
5.7 EVALUATION	9
SECTION 6: STRUCTURAL STABILITY	10
6.1 EVALUATION OF STRUCTURAL STABILITY	10
SECTION 7: ASSESSMENT/RECOMMENDATIONS	11
7.1 ASSESSMENT	11
7.2 RECOMMENDATION	11
<u>APPENDIX</u>	
A. PHOTOGRAPHS	
B. VISUAL INSPECTION CHECKLIST	
C. ENGINEERING DATA CHECKLIST	
D. HYDROLOGY AND HYDRAULIC ANALYSES	
E. PLATES	
F. GEOLOGY MAP	



TABLE OF CONTENTS  
(Continued)

G. STABILITY ANALYSES

H. REFERENCES

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Newtown-Hoffman Creeks Watershed  
Project - Floodwater Retarding  
Dam Site 1  
N.Y. 547

State Located: New York

County Located: Chemung

Stream: Newtown Creek (a tributary of  
Chemung River)

Date of Inspection: June 24, 1981 and July 15, 1981

ASSESSMENT


Based on the evaluation of the existing conditions, the condition of the Newtown-Hoffman Creeks Watershed Project - Floodwater Retarding Dam Site 1 is considered to be good. The examination of documents and visual observations did not reveal conditions which constitute a hazard to human life or property.

The spillway capacity was evaluated according to the recommended procedure and was found to pass the required spillway design flood of 100 percent of the Probable Maximum Flood (PMF). Therefore, the spillway capacity is rated as adequate.

The following recommendation should be implemented within three months from notification to the owner:

1. An emergency action plan should be developed, including a formal warning system to alert the downstream residents in the event of an emergency.

Assessment - Newtown-Hoffman Creeks Watershed Project - Floodwater  
Retarding Dam Site 1



A handwritten signature of Lawrence D. Andersen in cursive script.

Lawrence D. Andersen, P.E.  
Vice President  
D'Appolonia Consulting Engineers, Inc.  
Pittsburgh, Pennsylvania

Approved by:

A handwritten signature of Col. W. M. Smith, Jr. in cursive script.

Col. W. M. Smith, Jr.  
New York District Engineer

Date:


14 SEP 1981

NEWTOWN-HOFFMAN CREEKS WATERSHED PROJECT -  
FLOODWATER RETARDING DAM SITE 1

N.Y. 547

DEC I.D. 67A-3974

JUNE 24, 1981



OVERVIEW

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
NEWTOWN-HOFFMAN CREEKS WATERSHED PROJECT -  
FLOODWATER RETARDING DAM SITE 1  
N.Y. 547  
DEC I.D. NO. 67A-3974  
CHEMUNG RIVER BASIN  
CHEMUNG COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I Inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

The inspection was to evaluate the existing conditions of the subject dam to identify deficiencies and hazardous conditions, determine if they constitute hazards to life and property, and recommend remedial measures where necessary.

1.2 DESCRIPTION OF PROJECT

a. Dam and Appurtenances

Newtown-Hoffman Creeks Watershed Project - Floodwater Retarding Dam Site 1 consists of an earth embankment approximately 800 feet long with a maximum height of about 46 feet from the downstream toe. The embankment has a design crest width of 16 feet. The upstream slope of the top 10 feet is 3 horizontal to 1 vertical and is 3.5 horizontal to 1 vertical for the remaining height. A 10-foot-wide berm is located at normal pool elevation. The downstream slope is 2.5 horizontal to 1 vertical with a 20-foot-wide berm 30 feet below the dam crest.

The spillway facilities for the dam consist of a vegetated earth emergency channel located at the left abutment and a riser-type primary spillway located near the left abutment (looking downstream). The emergency spillway is a trapezoidal channel with a base width of 224 feet. The side slopes of the channel are 3 horizontal to 1 vertical. The control section of the emergency spillway is located in line with the axis of the dam, approximately nine feet below the dam crest level.

The primary spillway structures are comprised of a reinforced concrete intake riser which discharges into a 30-inch-diameter

reinforced concrete pipe, terminating at a plunge pool at the downstream toe. The discharge pipe is equipped with reinforced concrete antiseep collars.

The reservoir drain facilities consist of an 18-inch-diameter reinforced concrete pipe extending from the upstream toe to the primary spillway riser. Flow through the pipe is controlled by a manually operated sluice gate at the primary spillway riser.

b. Location

The dam is located on an unnamed tributary of Newtown Creek, which is a tributary of the Chemung River, approximately three-quarters of a mile south of Erin, in Erin Township, Chemung County, New York. Plate 1 illustrates the location of the dam.

c. Size Classification

The dam is classified to be of intermediate size based on its 46-foot height and maximum storage capacity of approximately 910 acre-feet.

d. Hazard Classification

The dam is classified to be in the high hazard category. About one mile downstream, Newtown Creek flows through a rural residential area which is considered to be within the potential floodplain of Newtown Creek.

It is estimated that failure of the dam under maximum pool level would cause loss of more than a few lives and significant property damage in this area.

e. Ownership

The dam is owned and operated by Chemung County: Mr. Stanley Benjamin, County Executive, J. H. Hazlett Building, 205 Lake Street, Elmira, New York 14901, (607) 739-3009.

f. Purpose of Dam

The dam is a floodwater retarding structure.

g. Design and Construction History

The dam was designed by the U.S. Department of Agriculture, Soil Conservation Service (SCS) in 1970. Construction of the dam was completed in January 1976.

h. Normal Operating Procedure

The reservoir is normally maintained at the crest level of the primary spillway riser at Elevation 1300.7. The emergency spillway crest is at Elevation 1321.2.

1.3 PERTINENT DATA

Elevations referred to in this section and subsequent sections of the report were obtained from design and as-built drawings.

a. <u>Drainage Area</u> (sq. mi.)	3.5
b. <u>Discharge at Dam</u> (cfs)	
Principal spillway at top of dam	145
Auxiliary spillway at top of dam	20400
Reservoir drain at top of dam	40 <sup>+</sup>
Total spillway capacity at top of dam	20545
c. <u>Elevation (USGS Datum)</u> (feet)	
Top of dam	1330.5
Auxiliary spillway crest	1321.2
Principal spillway crest	1300.7
Reservoir drain, invert	1289.0
d. <u>Reservoir</u> (acres)	
Surface area at top of dam	56.0
Surface area at crest of auxiliary spillway	38.0
Surface area at crest of principal spillway	6.5
e. <u>Storage Capacity</u> (acre-feet)	
Top of dam	910
Auxiliary spillway crest	610
Principal spillway crest	103
f. <u>Dam</u>	
Type	Earth embankment
Length	800 feet
Height	46 feet
Top width	16 feet
Side slopes	Downstream: 2.5H:1V Upstream: 3H:1V and 3.5H:1V
Zoning	No
Impervious core	No
Cutoff	Yes
Grout curtain	No
g. <u>Primary Spillway</u>	
Type	Drop Inlet
Length	15 feet (weir length)
Crest elevation	1300.7
h. <u>Emergency Spillway</u>	
Type	Trapezoidal earth channel
Length	224 feet
Crest elevation	1321.2

i. Regulating Outlet

Type

18-inch reinforced  
concrete pipe

Length

40 feet

Access

Accessible through  
riser

Regulating facilities

Sluice gate



## SECTION 2: ENGINEERING DATA

### 2.1 DATA AVAILABLE

Available information was obtained from New York State Department of Environmental Conservation, Dam Safety Division files, and from the files of the SCS in Syracuse, New York. Available information includes design, as-built drawings, and engineering reports.

### 2.2 GEOLOGY

The Newtown-Hoffman Creeks Watershed Project - Floodwater Retarding Dam Site 1 is located in the glaciated Allegheny Plateau section of the Appalachian Plateau Province. This section is characterized as a maturely dissected plateau with the features modified by continental glaciation. The modification consists of rounding off of high areas and deposition of glacial till in the valleys.

The dam site is near the axis of a northeast trending syncline (trending approximately north 70 degrees east). The folding is gentle with the maximum dip of the limbs one to two degrees. The dip of the strata are affected locally by the folding; however, regionally, the rock strata dip south to southwest at approximately 50 to 100 feet per mile. The most prominent fracture orientations in the region have a strike of north 30 degrees west with a vertical dip. A secondary fracture trace strikes north 80 degrees east.

The rock strata in the area consist of unconsolidated Pleistocene glacial till (Wisconsin Drift) underlain by strata of the Lower West Falls Group (Upper Devonian Age). The glacial till consists of a mixture of clay and silt with varying quantities of gravel. The glacial till is relatively thin on hilltops and slopes and thicker in the valleys, greater than 45 feet thick. The bedrock consists of a thick sequence of interbedded dark gray to black shale and siltstone which may be up to 2,000 feet thick.

The abutment slopes are relatively gentle and not susceptible to landslide slope movement, except near the base of the slope where minor sloughing of the glacial till may occur.

### 2.3 SUBSURFACE INVESTIGATION

A subsurface investigation was conducted by the SCS in 1970. This program consisted of 12 borings and 25 test pits. Boring and test pit logs are available in SCS files.

The subsurface conditions were described as a thick (36-foot to 45-foot) silty gravel till, overlain by lacustrine silt on the left abutment and floodplain. A thin deposit of alluvial gravel was above the silt and gravel till. Bedrock was not encountered during the investigation.

#### 2.4 EMBANKMENT AND APPURTENANT STRUCTURES

Plates 2 and 3 show the plan and the typical cross section of the dam. As shown in Plate 3, the dam consists of a homogeneous embankment incorporating a centrally located cutoff trench and an internal drainage system consisting of a trench drain beneath the downstream slope. Plate 4 shows the layout and the details of the trench drain. Most of the embankment is reported to consist of silty gravelly glacial till. A portion of the upstream slope and a section near the downstream toe of the slope consist of oversize rock fill.

Plate 5 shows the plan and the typical cross section of the primary spillway and reservoir drain facilities. Plates 6, 7, and 8 include selected subsurface investigation boring logs.

The spillway facilities were designed based on hydrologic and hydraulic analyses conducted by the SCS. The design calculations are available in SCS files.

#### 2.5 CONSTRUCTION RECORDS

The dam was constructed under the supervision of the SCS. Complete construction records are available in SCS files. No major post-construction changes were instituted.

#### 2.6 OPERATING RECORDS

Because the dam is an ungaged flood-retarding structure, no operating records are maintained for the dam. During severe weather conditions, the dam is monitored by the SCS and Chemung County personnel.

#### 2.7 EVALUATION OF DATA

The information obtained from the state and SCS files is considered to be adequate for Phase I inspection purposes.

## SECTION 3: VISUAL INSPECTION

### 3.1 FINDINGS

#### a. General

Visual inspections of the dam were conducted on June 24 and July 15, 1981. On both dates, the pool level was approximately at the primary spillway riser crest.

#### b. Embankment

No signs of distress, seepage, or misalignment were observed. While the crest of the dam is covered with grass, the upstream and downstream faces are covered with crown-vetch. There are two internal drainage pipes, both of which were dry. The top of the dam was surveyed relative to the emergency spillway crest elevation and was found to be in conformance with as-built elevations.

#### c. Primary Spillway

The primary spillway facilities consist of a concrete drop inlet structure discharging into a 30-inch reinforced concrete pipe terminating at a plunge pool at the downstream toe. Components of the primary spillway were in satisfactory condition.

#### d. Emergency Spillway

The emergency spillway is a trapezoidal vegetated earth channel located on the left abutment. The channel is in good condition. The grass cover is well established and adequately maintained. The approach and discharge channel were free of brush and trees or debris which could pose a potential for blockage of the spillway.

#### e. Reservoir Drain

The reservoir drain facilities consist of an 18-inch-diameter reinforced concrete pipe, extending from the upstream toe to the primary spillway riser. Flow through the pipe is controlled by a manually operated sluice gate. The gate system is reported to be operational, although operation was not observed.

#### f. Downstream Channel

The downstream channel below the primary spillway plunge pool is the natural stream bed. The channel appears to be stable in the near vicinity of the dam.

#### g. Reservoir

There are no visible signs of instability or sedimentation problems within the reservoir area.

### 3.2 EVALUATION

The dam was found to be in good condition. At this time, no conditions were observed that would require remedial action.

## SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

### 4.1 PROCEDURES

The reservoir is normally maintained at the crest level of the primary spillway. The dam is a flood-retarding structure and has no formal operating procedure.

### 4.2 MAINTENANCE OF THE DAM

The dam is maintained by Chemung County Soil and Water Conservation District and the maintenance condition of the dam is considered to be satisfactory.

### 4.3 WARNING SYSTEM IN EFFECT

No formal warning system exists for the dam.

### 4.4 EVALUATION

The maintenance condition of the dam is considered to be good. Development of an emergency action plan is considered to be advisable. It is reported by the SCS, Broome County office, that such a plan is currently being prepared.

## SECTION 5: HYDRAULIC/HYDROLOGY

### 5.1 DRAINAGE AREA CHARACTERISTICS

Newtown-Hoffman Creeks Watershed Project - Floodwater Retarding Dam Site 1 has a drainage area of 3.5 square miles. The watershed is comprised of woodlands and farmlands. Relief ranges from moderate to steep.

### 5.2 ANALYSIS CRITERIA

The PMF inflow hydrograph for the reservoir was determined using the Dam Safety Version of the HEC-1 computer program developed by the Hydrologic Engineering Center of the U.S. Army Corps of Engineers. The data used for the computer input are presented in Appendix D.

### 5.3 SPILLWAY CAPACITY

The spillway facilities for the dam consist of a primary and emergency spillway. The emergency spillway is a trapezoidal earth channel located on the left abutment. The base width of the channel is 224 feet. Based on the available head relative to the dam crest, the combined capacity of the primary and emergency spillways is calculated to be 20,545 cfs.

### 5.4 RESERVOIR CAPACITY

The dam impounds a reservoir with a storage capacity of 103 acre-feet at the primary spillway crest level (Elevation 1300.7), 468 acre-feet at the emergency spillway crest level (Elevation 1321.2), and 610 acre-feet at the top of the dam (Elevation 1330.5).

### 5.5 FLOODS OF RECORD

No data available.

### 5.6 OVERTOPPING POTENTIAL

The PMF inflow hydrograph was determined according to the recommended criterion and was found to have a peak flow of 8960 cfs. The hydrograph was routed through the dam using the capacity rating data included in the design files and the dam was found to pass full PMF with the reservoir at Elevation 1327.0, leaving 3.5 feet of freeboard to the design dam crest level.

### 5.7 EVALUATION

The spillway can pass the recommended spillway design flood of full PMF without overtopping the embankment; therefore, the spillway capacity is classified to be adequate according to the recommended criteria.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observations

As discussed in Section 3, the field observations did not reveal any signs of distress that would significantly affect the stability of the dam at this time. However, it should be understood that because the dam is a flood control facility and was at normal low pool level at the time of inspection, it was not under maximum loading conditions which would occur only during the passage of major floods.

#### b. Design and Construction Data

The dam was designed based on geological and geotechnical studies, which included subsurface investigations, laboratory materials testing and engineering analyses. A SCS memorandum, dated February 4, 1971 and included in Appendix G, summarized the findings and results of the design investigation.

The stability analyses were performed using the Swedish Circle and sliding block methods. The total stress strength parameters used were: internal friction angle, 15 degrees; cohesion, 425 pounds per square foot; saturated and submerged unit weights, 137.5 and 75.0 pounds per cubic foot, respectively.

Factors of safety were reported to be 1.39 for the upstream slope under rapid drawdown conditions, and 1.52 for the downstream slope, under steady state seepage. Available information was reviewed and found to be adequate.

The calculated factors of safety for this dam are in excess of the minimum factors of safety recommended by the Corps of Engineers. The dam is, therefore, considered to have an adequate safety factor for stability.

#### c. Postconstruction Changes

None reported.

#### d. Seismic Stability

The dam is located in Seismic Zone 1. Based on the recommended criteria for evaluation of seismic stability of dams, the structure is presumed to present no hazard from earthquakes.

## SECTION 7: ASSESSMENT/RECOMMENDATIONS

### 7.1 ASSESSMENT

#### a. Safety

Visual observations indicate that Newtown-Hoffman Creeks Watershed Project - Floodwater Retarding Dam Site 1 is in good condition. No conditions were observed that would significantly affect the overall performance of the structure at this time. However, as previously noted, the dam was not inspected under its maximum loading condition which would occur when the reservoir is filled during major storms.

The spillway capacity was evaluated according to the recommended procedure and was found to pass the required spillway design flood of full PMF without overflowing the embankment; therefore, the spillway capacity is classified to be adequate.

#### b. Adequacy of Information

Available information, in conjunction with visual observations, is considered to be sufficient to make a Phase I evaluation.

#### c. Need for Additional Investigations

No additional investigation is considered to be required at this time.

#### d. Urgency


The action recommended below should be implemented within three months from notification to the owner.

### 7.2 RECOMMENDATION

1. An emergency action plan should be developed, including a formal warning system to alert the downstream residents in the event of an emergency.

APPENDIX A  
PHOTOGRAPHS







PHOTOGRAPH NO. 1  
Downstream Slope (looking west)



PHOTOGRAPH NO. 2  
Dam Crest (background)  
Emergency Spillway (foreground)  
(looking east)



PHOTOGRAPH NO. 3  
Primary Spillway Riser



PHOTOGRAPH NO. 4  
Primary Spillway Discharge Pipe



PHOTOGRAPH NO. 5  
Rural Residential Area  
(0.6 mile downstream)



PHOTOGRAPH NO. 6  
Rural Residential Area  
(1.0 mile downstream)

APPENDIX B  
VISUAL INSPECTION CHECKLIST

APPENDIX B  
VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam Newtown-Hoffman Creeks Watershed Project -  
Floodwater Retarding Dam Site 1

Fed. I.D. # N.Y. 547 DEC Dam No. 67A-3974

River Basin Chemung River Basin

Location: Three-quarter mile south of Erin, Chemung County

Stream Name Tributary of Newtown Creek

Tributary of Chemung River

Latitude (N) 42° 10.4' Longitude (W) 76° 40.0'

Type of Dam Earth

Hazard Category High

Date(s) of Inspection June 24, 1981 and July 15, 1981

Weather Conditions Sunny, Temp. 60 degrees

Reservoir Level at Time of Inspection El. 1301.0 <sup>+</sup>

b. Inspection Personnel Lawrence Andersen, P.E.; James Poellot,  
P.E.; Bilgin Erel, P.E.; and Michael Bort

c. Persons Contacted (Including Address & Phone No.)   
Mr. Stanley Benjamin, Chemung County Executive, J. H. Hazlett  
Building, 205 Lake Street, Elmira, New York 14901,  
(607) 739-3009

d. History:

Date Constructed Jan. 1976 Date(s) Reconstructed N/A

Designer USDA Soil Conservation Service

Constructed by Carl Simone, Inc.

Owner Chemung County, New York

2) Embankment

a. Characteristics

(1) Embankment Material Earth

(2) Cutoff Type Trapezoidal cutoff trench, bottom width varies from 12 feet to 20 feet, to varied depths.

(3) Impervious Core None

(4) Internal Drainage System Trench drain equipped with two 8-inch-diameter perforated drainage pipes.

(5) Miscellaneous --

b. Crest

(1) Vertical Alignment Good (0.1 to 0.7 foot above design elevation)

(2) Horizontal Alignment Good

(3) Surface Cracks None

(4) Miscellaneous --

c. Upstream Slope

(1) Slope (Estimate) Top of dam to El. 1321.2, 3H:1V; El. 1321.2 to toe, 3.5H:1V (as designed)

(2) Undesirable Growth or Debris, Animal Burrows None

(3) Sloughing, Subsidence or Depressions None

(4) Slope Protection Vegetated Slope to normal pool, riprap  
(oversized rock) to toe of dam.

(5) Surface Cracks or Movement at Toe None

d. Downstream Slope

(1) Slope (Estimate) 2.5H:1V (as designed and measured)

(2) Undesirable Growth or Debris, Animal Burrows None

(3) Sloughing, Subsidence or Depressions None

(4) Surface Cracks or Movement at Toe None

(5) Seepage None

(6) External Drainage System (Ditches, Trenches, Blanket)  
None

(7) Condition Around Outlet Structure Good

(8) Seepage Beyond Toe None

e. Abutments - Embankment Contact

No problems observed.

(1) Erosion at Contact None

(2) Seepage Along Contact None

3) Drainage System

a. Description of System A trench drain under the downstream toe of the dam equipped with two 8-inch-diameter perforated pipes, one for each side of the dam.

b. Condition of System Only the downstream end of the pipes were visible.

c. Discharge from Drainage System None

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, etc.)

None



5) Reservoir

- a. Slopes Moderate slopes, no problems observed.
- b. Sedimentation No problems observed.
- c. Unusual Conditions Which Affect Dam None observed.

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) Rural  
residential area (10-15 homes) approximately one mile  
downstream of the dam.
- b. Seepage, Unusual Growth None
- c. Evidence of Movement Beyond Toe of Dam None
- d. Condition of Downstream Channel Good

7) Spillway(s) (Including Discharge Conveyance Channel)

- a. General Service Spillway: Concrete riser discharging into  
a 30-inch-diameter reinforced concrete pipe.  
Auxiliary Spillways: 224-foot-wide trapezoidal  
vegetated earth channel on left abutment.
- b. Condition of Service Spillway Good

c. Condition of Auxiliary Spillway Good

d. Condition of Discharge Conveyance Channel Good

8) Reservoir Drain/Outlet

Type: Pipe X Conduit          Other         

Material: Concrete X Metal          Other         

Size: 18-inch-diameter Length 40 feet

Invert Elevations: Entrance 1289.0 Exit 1288.8

Physical Condition (Describe): Not observable.

Material:         --        

Joints:         --         Alignment         --        

Structural Integrity:         --        

Hydraulic Capability:         --        

Means of Control: Gate X Valve          Uncontrolled         

Operation: Operable X Inoperable          Other         

Present Condition (Describe): The reservoir drain system  
is reported operable.

9) Structural

- a. Concrete Surfaces The concrete riser appears to be in  
good condition.
- b. Structural Cracking None observed.
- c. Movement - Horizontal & Vertical Alignment (Settlement)  
None observed.
- d. Junctions with Abutments or Embankments   
Not visible.
- e. Drains - Foundation, Joint, Face   
No problems observed.
- f. Water Passages, Conduits, Sluices   
N/A
- g. Seepage or Leakage None observed.

- h. Joints - Construction, etc. No problems observed.
- i. Foundation Not visible.
- j. Abutments N/A
- k. Control Gates Reported operable.
- l. Approach & Outlet Channels Good
- m. Energy Dissipators (Plunge Pool, etc.) Plunge pool in  
satisfactory condition.
- n. Intake Structures Good
- o. Stability N/A
- p. Miscellaneous ---

10) Appurtenant Structures (Power House, Lock, Gatehouse, Other)

a. Description and Condition None

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

APPENDIX C  
ENGINEERING DATA CHECKLIST

APPENDIX C  
ENGINEERING DATA CHECKLIST  
NAME OF DAM: NEWTOWN-HOFFMAN CREEKS WATERSHED  
PROJECT - FLOODWATER RETARDING DAM SITE 1

AREA-CAPACITY DATA:

	<u>Elevation</u> (feet)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-feet)
1) Top of Dam	<u>1330.5</u>	<u>56.0</u>	<u>910</u>
2) Design High Water (Max. Design Pool)	<u>1327.0</u>	<u>49.5</u>	<u>610</u>
3) Auxiliary Spillway Crest	<u>1321.2</u>	<u>38.0</u>	<u>468</u>
4) Service Spillway Crest	<u>1300.7</u>	<u>6.5</u>	<u>103</u>

DISCHARGES

	<u>Discharge</u> (cfs)
1) Average Daily	<u>6 ±</u>
2) Auxiliary Spillway at Maximum High Water (Top of Dam)	<u>20400</u>
3) Auxiliary Spillway at Design High Water (El. 1327.0)	<u>8860</u>
4) Principal Spillway at Auxiliary Spillway Crest Elevation 1321.2	<u>140</u>
5) Low Level Outlet	<u>40 ±</u>
6) Total of All Facilities at Maximum High Water	<u>20545</u>
7) Maximum Known Flood	<u>Unknown</u>
8) At Time of Inspection	<u>15 ±</u>

DAM: Newtown-Hoffman Creeks Watershed Project - Floodwater  
Retarding Dam Site 1

CREST ELEVATION: 1330.5

Type: Earth

Width: 16 feet Length: 800 feet

Spillover: Concrete riser and vegetated earth channel.

Location: Concrete riser near the left abutment, earth channel  
on left abutment.

SPILLWAY:

SERVICE		AUXILIARY
<u>1300.7</u>	Elevation	<u>1321.2</u>
<u>Concrete drop inlet</u>	Type	<u>3H:1V trapezoidal earth channel</u>
<u>15-foot weir</u>	Width	<u>224 feet</u>
	Type of Control	
<u>Uncontrolled</u>	<u>Uncontrolled</u>	<u>Uncontrolled</u>
	Controlled	
<u>N/A</u>	Type	<u>N/A</u>
	(Flashboards; Gate)	
<u>N/A</u>	Number	<u>N/A</u>
<u>N/A</u>	Size/Length	<u>400<sup>±</sup> feet</u>
	Invert Material	<u>N/A</u>
	Anticipated Length of Operating Service	<u>Unknown</u>
<u>273<sup>±</sup> feet</u>	Chute Length	<u>N/A</u>
<u>13<sup>±</sup> feet</u>	Height Between Spillway Crest and Approach Channel Invert (Weir Flow)	<u>7<sup>±</sup> feet</u>



Hydrometeorological Gages:

Type: None

Location: N/A

Records:

Date - N/A

Max. Reading - N/A

FLOODWATER CONTROL SYSTEM:

Warning System: None

Method of Controlled Releases (Mechanisms):

None

DRAINAGE AREA: 3.5 square miles

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: Forest and farmland

Terrain - Relief: Moderate to steep slopes

Surface - Soil: Low permeability

Runoff Potential (existing or planned extensive alterations to existing surface or subsurface conditions)

Moderate to high runoff potential (SCS Hydrological

Curve Number (CN) 75 was used in the original design

calculations).

Potential Sedimentation Problem Areas (natural or man-made; present or future)

None observed.

Potential Backwater Problem Areas for Levels at Maximum Storage Capacity Including Surcharge Storage:

None observed.

Dikes - Floodwalls (overflow and nonoverflow) - Low Reaches Along the Reservoir Perimeter:

Location: None

Elevation:

Reservoir:

Length at Maximum Pool: 2,650<sup>±</sup> feet; at normal pool,

950<sup>±</sup> feet

Length of Shoreline at Normal Pool: 2,400<sup>±</sup> feet

APPENDIX D  
HYDROLOGY AND HYDRAULIC ANALYSES

HYDROLOGY AND HYDRAULIC ANALYSIS  
DATA BASE

NAME OF DAM: Newtown-Hoffman Creeks Watershed Project-  
Floodwater Retarding Dam Site 1 (NY DEC 67A-3984)

PROBABLE MAXIMUM PRECIPITATION (PMP) = 21.1 INCHES/24 HOURS<sup>(1)</sup>

STATION	1	2	3	4	5
Station Description	Site 1 Drainage Area	Site 1 Dam			
Drainage Area (square miles)	3.5	--			
Cumulative Drainage Area (square miles)	3.5	3.5			
Adjustment of PMP for Drainage Area (%)					
6 Hours	111	--			
12 Hours	123	--			
24 Hours	132	--			
48 Hours	142	--			
72 Hours	--	--			
Snyder Hydrograph Parameters					
$C_p/C_c$ (2)	0.72/1.7	--			
L (miles) (3)	1.99	--			
$L_{ca}$ (miles) (3)	0.85	--			
$t_p = C_c(L \cdot L_{ca})^{0.3}$ (hours)	2.0	--			
Spillway Data					
Crest Length (ft)	--	See spillway capacity			
Freeboard (ft)	--	rating			
Discharge Coefficient	--	calculations			
Exponent	--				

(1) Hydrometeorological Report 33 (Figure 1), U.S. Army, Corps of Engineers, 1956.

(2) Snyder's Coefficients (see attached calculations).

(3) L = Length of longest water course from outlet to basin divide.  
     $L_{ca}$  = Length of water course from outlet to point opposite the centroid of drainage area.



PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS									
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9	
				.20	.30	.40	.50	.60	.70	.80	.90	1.00	
HYDROGRAPH AT	1	3.46	1	1791.	2687.	3583.	4474.	5374.	6270.	7166.	8062.	8957.	
	(	8.96)	(	50.73)	76.09)	101.46)	126.82)	152.19)	177.55)	202.91)	228.28)	253.64)	
ROUTED TO	2	3.46	1	1105.	2446.	3467.	4350.	5284.	6177.	7077.	7975.	8860.	
	(	8.96)	(	31.29)	69.27)	98.17)	123.62)	149.63)	174.91)	200.39)	225.82)	250.89)	

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1300.70 0. 0.	SPILLWAY CREST 1300.70 0. 0.	TOP OF DAM 1330.50 850. 20400.	TIME OF FAILURE HOURS	
RATIO OF PMF	MAXIMUM RESERVOIR W.S.CLEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS
.20	1322.83	0.00	476.	1105.	0.00	41.25
.30	1323.82	0.00	518.	2446.	0.00	42.25
.40	1324.45	0.00	546.	3467.	0.00	42.00
.50	1325.00	0.00	571.	4366.	0.00	42.00
.60	1325.47	0.00	592.	5284.	0.00	41.75
.70	1325.88	0.00	611.	6177.	0.00	41.75
.80	1326.28	0.00	630.	7077.	0.00	41.75
.90	1326.63	0.00	647.	7975.	0.00	41.75
1.00	1326.98	0.00	664.	8860.	0.00	41.75

# D'APPOLONIA

CONSULTING ENGINEERS, INC.

By WTC Date 2/17/81 Subject NEWTOWN-HOFFMAN CREEK SITE 1 Sheet No. 1 of 4  
Chkd. By SRF Date 23 AUG 81 SPILLWAY RATING Proj. No. 30-773

## SPILLWAY CAPACITY RATING

REFERENCE : DESIGN OF SMALL DAM, 2<sup>nd</sup> EDITION. P 553

ASSUMPTION (1) SPECIFIC ENERGY  $H_E = d + \frac{V^2}{2g}$

(2) CRITICAL FLOW AT CONTROL SECTION.

$d = d_c$  ;  $V = V_c$  and  $H_E = \text{LAKE LEVEL}$

NO OTHER MINOR LOSSES ARE CONSIDERED

(3) D/S SLOPE IS STEEPER THAN CRITICAL SLOPE.

FROM P 553 OF REF:

$$V_c = \sqrt{\frac{b + z d_c}{b + 2 z d_c} d_c g} \quad \text{--- EQ-1}$$


$$H_E = d_c + \frac{V_c^2}{2g} = d_c + \left( \frac{b + z d_c}{b + 2 z d_c} d_c g \right) \left( \frac{1}{2g} \right)$$

$$= \frac{(3b + 5z d_c) d_c}{2b + 4z d_c}$$

$$d_c = \frac{-(3b - 4H_E z) + \sqrt{(3b - 4H_E z)^2 + (4H_E z)(10b)}}{10z}$$

$$A_c = (z d_c + b) d_c \quad \text{--- EQ-3}$$

$$Q_c = A_c V_c \quad \text{--- EQ-4}$$



SECTION A-A

--- EQ-2

LAKE ELEVATION FEET	$H_E$ FT	$d_c$ EQ-2 FT	$A_c$ EQ-3 FT <sup>2</sup>	$V_c$ EQ-1 FPS	$Q_c$ EQ-4 CFS	EMERGENCY Spillway
1321.2	0	0	0	0	0	b = 224
1321.7	0.5	0.3	75.1	3.3	246	z = 3
1322.2	1.0	0.7	151.1	4.6	698	
1323.2	2.0	1.3	305.8	6.5	1992	
1324.2	3.0	2.0	464.1	8.0	3692	
1325.2	4.0	2.7	625.9	9.2	5734	
1326.2	5.0	3.4	791.4	10.2	8083	
1327.2	6.0	4.1	960.5	11.2	10718	
1328.2	7.0	4.8	1133.3	12.0	13623	
1329.2	8.0	5.4	1309.7	12.8	16786	
1330.2	9.0	6.1	1489.7	13.6	20201	
1331.2	10.0	6.8	1673.4	14.3	23359	
1332.2	11.0	7.5	1860.8	14.9	27753	



# D'APPOLONIA

CONSULTING ENGINEERS, INC.


By WTC Date 8/17/81 Subject VENTON-HOFFMAN SITE 1

Sheet No. 2 of 4

Chkd. By SRP Date 26 AUG 81 SPILLWAY RATING

Proj. No. 30-778

## PRIMARY SPILLWAY DISCHARGE RATING



WEIR FLOW

$$Q_1 = CL (H)^{1.5}$$

$$= (3.22)(15)(W.L. ELEV. - 1300.7)^{1.5}$$

$$= 48.3 (W.L. ELEV. - 1300.7)^{1.5} - EQ - 5$$

PIPE FLOW

$$H_f = \left[ \frac{(2.5204)(1+K_e)}{D^4} + \frac{466.18 n^2 L}{D^{16/3}} \right] \left( \frac{Q_2}{10} \right)^2 \quad \text{(FROM P. 567 DESIGN OF SMALL DAM, 2ND ED.)}$$

$$(W.L. ELEV. - 1282.7) = \left[ \frac{(2.5204)(1.9)}{(2.5)^4} + \frac{(466.18)(0.012)^2(272.7)}{(2.5)^{16/3}} \right] \left( \frac{Q_2}{10} \right)^2$$

$$Q_2 = 19.5848 \sqrt{W.L. ELEV. - 1282.7} - EQ - 6$$

# D'APPOLONIA

CONSULTING ENGINEERS, INC.


By WTC Date 8-17-81 Subject NEWTOWN-HOFFMAN SITE 1 Sheet No. 3 of 4  
 Chkd. By SRP Date 26 AUG 81 Proj. No. 30-778

LAKE LEVEL ELEVATION	PRIMARY SPILLWAY			EMERGENCY SPILLWAY	COMBINED SPILLWAY CAPACITY cfs
	Q <sub>1</sub> cfs EQ-5	Q <sub>2</sub> cfs EQ-6	Q <sub>3</sub> cfs	Q <sub>4</sub> cfs EQ-4	
1300.7	0	0	0	0	0
1300.2	1.5	<del>83.3</del>	1.5	↑	2
1301.0	7.9	<del>83.8</del>	7.9	↑	8
1301.2	17.1	<del>84.2</del>	17.1	↑	17
1301.4	28.3	<del>84.7</del>	28.3	↑	28
1301.6	41.2	<del>85.1</del>	41.2	↑	41
1301.8	55.7	<del>85.6</del>	55.7	↑	56
1302.0	71.6	<del>86.0</del>	71.6	↑	72
1302.2	<del>88.7</del>	86.5	86.5	↑	87
1302.4	<del>107.1</del>	86.9	86.9	↑	87
1304		90.4	90.4	↑	90
1308		98.5	98.5	↑	99
1312		106.0	106.0	↑	106
1316		113.0	113.0	↑	113
1320		119.6	119.6	↓	120
1321.2			121.5	0	122
1321.7			122.3	246	368
1322.2			123.1	698	821
1323.2			124.6	1392	2117
1324.2			126.2	3692	3818
1325.2			127.7	5734	5862
1326.2			129.2	2023	8212
1327.2			130.6	10718	10849
1328.2			132.1	13623	13755
1329.2			133.6	16786	16920
1330.2			135.0	20301	20336
1331.2			136.4	23859	23995
1332.2			137.8	27752	27896

# D'APPOLONIA

CONSULTING ENGINEERS, INC.


By WTC Date 8/17/81 Subject NEWTOWN - HOFFMAN CREEK SITE 1 Sheet No. 4 of 4  
Chkd. By SRP Date 26 AUG 81 SPILLWAY RATING Proj. No. 80-778




APPENDIX E

PLATES

DRAWN BY: AEC  
 CHECKED BY: JHP  
 APPROVED BY: JHP  
 7/24/81  
 7-24-81  
 DRAWING 80-778-B36  
 NUMBER



**KEY PLAN**



**REFERENCES**

1. U.S.G.S 7.5 MIN. VAN ETEN, NY. QUADRANGLE  
DATED: 1969, SCALE 1:24000
2. U.S.G.S 7.5 MIN. ERIN, NY. QUADRANGLE  
DATED: 1969, SCALE 1:24000

RURAL RESIDENTIAL AREA


NEWTOWN-HOFFMAN WATERSHED PROJECT  
FLOODWATER RETARDING DAM - SITE I

APPROXIMATE  
WATERSHED AREA

PLATE I


NEWTOWN-HOFFMAN WATERSHED PROJECT  
FLOODWATER RETARDING DAM-SITE I  
VICINITY, FLOOD PLAIN & WATERSHED MAP

SCALE




**D'APOLONIA**

DRAWN BY	G. J. G.	CHECKED BY	B. E.	DRAWING NUMBER	80-778-B37
	5-27-81	APPROVED BY	J. H. D.		7-29-81



**SECTION OF DIVERSION (not to scale)**

1. Section at top of emergency spillway cut slope.
2. Slope 0.01 Ft/Ft varies to 2% - .025/ft
3. Final location to be established in the field by the engineer at time of construction.





# BENCH MARK DESCRIPTION


BM # 6 Nail in SCS Disc on Power Pole NYS EGB4781 Elev. 1330.83  
 BM 101 East Monument - Station 15+72.3  
 Bronze Cap set in concrete approx. 50 S.W. of intersection of Marsh Rd. and Greenbush Rd. Elev. 1345.68

## LEGEND

- Design High Water
- Sediment Pool
- Fence Line (Existing)
- Buildings
- Park Road
- Hub (Traverse)
- Bench Mark
- Power Line
- Stream
- Contour Line
- Drill Hole
- Test Pit (Logged & Sampled)
- Test Pit (Logged Only)
- Diversion



WEST MONUMENT TIES



EAST MONUMENT TIES

## SCISS DETAILS

See sheets 20, 21, and 22 for descriptions of drill holes and test pits shown on sheets 3, 5, 6, 7, 8, and 10.

AS BUILT

1-28-76

2' CONTOUR INTERVAL  
 0 50 100 200  
 SCALE IN FEET

NEWTOWN-HOFFMAN CREEKS  
 WATERSHED PROJECT  
 FLOODWATER RETARDING DAM SITE 1  
 CHEMUNG COUNTY, NEW YORK  
 PLAN OF STRUCTURAL WORKS

U. S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE


Designed by	W. A. RIEGEL	Date	12/71	Approved by	
Drawn by	D. ANGELO	Date	12/71	Field	
Typed		Date		Time	
Sheet	3	Drawing No.	NY-2284-P		

PLATE 2

D'APPOLONIA



DRAWN BY G. J. G. CHECKED BY JAF 7/29/37 DRAWING 80-778-B38  
 5-27-81 APPROVED BY JAF 7-29-81



LED FILL

MATERIAL 1/	MAX ROCK SIZE 2/	MAX LIFT 3/	MIN. REL. C. WATER CONTENT 4/	COMPACTION 5/	
				CLASS	DEFINITION
GC-GM AND CL-M GLACIAL TILL AS REPRESENTED BY TP 204 FROM C 5 TO 11.0 TP 205 " 1.0 TO 14.4 TP 210 " 1.6 TO 14.3	6"	8"	OPTIMUM	A	100% OF MAXIMUM DENSITY BY ASTM D-698 METHOD A

- 1/ The placement table indicates estimated use of materials.
- 2/ a) Maximum rock size in backfill compacted by means of manually directed power tampers or plate vibrators shall be 3".  
b) oversize material (6" to 18" inclusive) placed in the earth fill shall be raked to the portion of the dam labeled OVERSIZE ROCK SECTIONS as shown on the drawings.  
c) Maximum lift thickness prior to compaction. The maximum lift thickness of the oversize rock section shall be no greater than 18" prior to compaction.
- 3/ Water content at time of compaction.
- 4/ a) For typical compaction curve see sheet 22.  
b) Use CLASS C compaction in areas of the dam containing oversize mat'l.
- 5/ CLASS C compaction shall consist of a minimum of three passes per lift of fill by a tamping roller exerting a min. contact pressure of 450 PSI, or equivalent as approved by the engineer. The final number of passes required will be determined by the engineer.

#### CONSTRUCTION DETAILS

- 1 OVERSIZE ROCK SECTION boundaries are approximate. Adjustments will be made by the engineer to utilize available material.
- 2 Material placed in the OVERSIZE ROCK SECTIONS shall consist of oversize mat'l raked from the earthfill. These sections shall be essentially free of materials less than 3". OVERSIZE ROCK SECTION above ELEV. 1300.0 may be relocated so as to be exposed at the upstream slope of the dam as determined by the engineer.
- 3 Topsoil that is suitable for use and not used on the specified areas of the emergency spillway shall be incorporated within the slopes of the earth fill as directed by the engineer. The source of the topsoil shall be within the required excavations.







PLATE 3


D'APPOLONIA

DRAWN BY	G. J. G.	CHECKED BY	13E	7/2/81	DRAWING NUMBER 80-778-B39
	5-27-81	APPROVED BY	JMP	7-2-81	






SECTION BB EE



SECTION CC DD



# DRAINAGE SYSTEM DETAILS

1. ASBESTOS CEMENT DRAIN PIPE SHALL CONFORM TO SPECIFICATION 545 AND SHALL BE 8" DIA PRESSURE PIPE CLASS 200.
2. THE PROFILES AT THE BOTTOM OF ALL EXCAVATIONS AS SHOWN ARE ONLY APPROXIMATE THE REQUIRED FINISHED GRADES WILL BE ESTABLISHED IN THE FIELD BY THE ENGINEER AT TIME OF CONSTRUCTION.

## QUANTITY SUMMARY

417	CU YDS DRAIN FILL I (FINE)
446	CU YDS DRAIN FILL II (COARSE)
333	LN FT STRAIGHT SECTION OF 8" DIA PERFORATED ASBESTOS CEMENT PIPE
52	LN FT STRAIGHT SECTION OF 8" DIA NON-PERFORATED ASBESTOS CEMENT PIPE
8	END CAPS
2	90° BEND- 8" DIA CAST IRON

## GRAIN SIZE DESCRIPTION FOR DRAIN FILL

1. DRAIN FILL I FINE SHALL MEET THE GRADATION OF ASTM C33-67 FOR FINE AGGREGATE. IN ADDITION THE PERCENTAGE OF MATERIAL IN DRAIN FILL I FINER THAN A #200 SIEVE SHALL NOT BE MORE THAN (3) PERCENT.
2. DRAIN FILL II COARSE SHALL MEET THE GRADATION OF SIZE DESIGNATION 1 AS SHOWN IN TABLE 703-4 OF THE JANUARY 2, 1973 STANDARD SPECIFICATIONS OF THE NEW YORK STATE DEPARTMENT OF TRANSPORTATION. IN ADDITION THE PERCENTAGE OF MATERIAL IN DRAIN FILL II FINER THAN A #200 SIEVE SHALL NOT BE MORE THAN THREE (3) PERCENT.

**AS BUILT** 1-28-76

NEWTOWN HOFFMAN CREEKS  
WATERSHED PROJECT  
FOODWATER RETARDING DAM SITE I  
CHEMUNG COUNTY NEW YORK  
DRAINAGE SYSTEM


U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE


Designed	W. A. RIEGEL	Date	7/71	Approved by	
Drawn	M. E. KORACH	Date	7/71		
Checked	E. BWP UNIT	Date	2/72		
				Project No.	10 NY-2284-P

PLATE 4

**D'APPOLONIA**

DRAWN BY	G. J. G.	CHECKED BY	BE
	5-27-81	APPROVED BY	JMP





JOINT NO	DIST FROM OUTLET	INVERT OF 30 DIA PIPE	SLOPE FT./FT.	
0	0	1282.18	0.0000	
1	20	1282.18		12.83.16
2	40	1282.18		12.83.16
3	60	1284.13		12.84.14
4	80	1284.59		
5	100	1285.03		
6	120	1285.43		12.85.44
7	140	1285.82		
8	160	1286.17		
9	180	1286.50		
10	200	1286.80		12.86.81
11	220	1287.08		
12	240	1287.35		
13	260	1287.55		
RISER	274	1287.70		12.87.68

Above dimensions for lengths of pipe are based on nominal lengths and do not include creep

CELLAR	DIST FROM OUTLET	INVERT OF 30 DIA PIPE
I	90	1284.81
II	110	1285.22
III	130	1285.82
IV	150	1286.99
V	170	1286.34
VI	190	1286.66
VII	210	1286.95
VIII	230	1287.21
IX	250	1287.45

#### RIPRAP DETAILS

LOOSE ROCK RIPRAP SHALL BE WELL GRADED FROM A MAXIMUM OF 24" TO A MINIMUM OF 6" 35% OF THE TOTAL WEIGHT TO BE FRAGMENTS HEAVIER THAN 350 LBS. AVERAGE WEIGHT OF THE FRAGMENTS SHALL BE 100-220 LBS. NOT MORE THAN 10% OF THE TOTAL WEIGHT TO BE FRAGMENTS LIGHTER THAN 35 LBS.


#### BEDDING DETAILS

Bedding shall meet the gradation requirements for drain fill II (coarse) as shown on sheet B.

When pipe is supplied in lengths other than shown the engineer will provide the contractor with a revision of this sheet.

For further details of 30" dia reinforced concrete pressure pipe see sheet 18.

TOP OF SETTLED FILL ELEV 1330.5



ELEV 13000  
ELEV 1299.5

94.0'  
2.5

REIN. CONC. PIPE  
TAIL SHEET 17

J-7 J-6 J-5 J-4 J-3 J-2

CL. 352 ELEV 1287.5

PLUNGE POOL  
ELEV 1282.7

89.6'  
ELEV 1279.8  
ELEV 1282.0  
ELEV 1274.4

35.33 REIN. CONC. CRADLE  
DETAIL SHT 18  
GM

272.7'  
160.6'

CL. ML - GC GM

AS BUILT

1-28-76

NEWTOWN-HOFFMAN CREEKS  
WATERSHED PROJECT  
FLOODWATER RETARDING DAM SITE-1  
CHEMUNG COUNTY, NEW YORK  
PLAN PROFILE OF PRINCIPAL SPILLWAY

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

Designed by W. A. RIEGEL	Date 10/71	Reviewed by
Drawn by D. BURDICK	Date 11/71	Checked by
Checked by E. B. W. UNIT	Date 2/72	NY-2284-P

PLATE 5

D'APPOLONIA

**DRAWN BY**

8	21.9
84	
87	
88	
89	
RM 151	
33	
46	
56	
39	
34	
45	
36	
30	
1.8	
48	
31	
28	
47	
36	
62	
RM 152	
5	
21	
22	
12	
107	
93	
61	
68	
24	
63	
61	
86.5	
63	
85	
143	
106	
113	
163	
172	
RM 153	
20	
34	
45	
82	
82	
29	
32	
23	
31	
123	
24	
56	
112	
180	
71	
73	

0.0  
1.0  
60% slightly plastic fines,  
slight permeability; hard  
CL-ML  
1.0  
60% slightly plastic fines,  
slight permeability; v. stiff  
(b > 100); varied line of  
CL-ML  
14.5  
0.0  
1.0  
60% slightly plastic fines,  
slight permeability; hard  
CL-ML  
1.0  
55% slightly plastic fines,  
moist; slight permeability;  
(b > 100); till; CL-ML  
21.5  
0.0  
1.0  
60% slightly plastic fines,  
slight permeability; hard  
CL-ML  
2.5  
55% slightly plastic fines,  
slight permeability; v. stiff  
(b > 100); till; CL-ML  
36.5  
0.0  
0.5  
60% slightly plastic fines,  
slight permeability; v. stiff  
CL-ML  
1.5  
55% slightly plastic fines,  
slight permeability; hard  
CL-ML  
19.0  
75% slightly plastic fines,  
permeability; v. stiff to hard  
(b > 100); lacustrine; CL-ML  
32.0  
55% slightly plastic fines,  
slight permeability; hard consistency  
CL-ML  
42.0

NH 214. Pr. Sp. 5/18/70. B.S. 1282.2		0.0
Topsoil		1.0
Silt, gravelly w/sand Approx. 35% gravel, 35% sand, 60% slightly plastic fines, LL=23, PI=6 Mottled (gray-brown); moist; slight permeability; hard consistency (b=64); subsoil; CL-ML		3.0
Silt, w/gravel and sand Approx. 35% gravel, 35% sand, 55% slightly plastic fines, LL=20, PI=6 Brown, grayish brown; gray; moist; slight permeability; hard consistency (b=67 to 63); till; CL-ML		2.5
NH 215. Pr. Sp. 5/18/70. B.S. 1282.4		0.0
Topsoil		1.0
Silt, gravelly w/sand Approx. 35% gravel, 35% sand, 65% slightly plastic fines, LL=23, PI=6 Mottled (gray-brown); moist; slight permeability; hard consistency (b=64); subsoil; CL-ML		3.5
Silt, gravelly w/sand Approx. 35% gravel, 35% sand, 55% slightly plastic fines, LL=20, PI=6 Brown to grayish brown; moist to wet; slight permeability; v. stiff to hard (b=16 to 62); till; CL-ML		27.0
NH 216. Pr. Sp. 5/18-14-16/70. B.S. 1282.7		0.0
Topsoil		1.5
Gravel, silty w/sand Approx. 35% gravel, 40% sand, 30% non plastic fines Brown; saturated; rapid permeability; medium density (b=41 to 22); alluvium; OH		4.5
Silt w/sand gravel and sand Approx. 35% gravel, 35% sand, 75% slightly plastic fines, LL=27, PI=6 Brown; moist; slight permeability; stiff to hard (b=12 to > 100); lacustrine; CL-ML		10.5
Gravel, silty w/sand Approx. 35% gravel, 35% sand, 35% slightly plastic fines, LL=20, PI=6 Brown to gray; moist to wet; slight permeability (0.00 fpd); medium to v. dense (b=24 to > 100); till; OC-CH		30.5
NH 217. Pr. Sp. 5/18/70. B.S. 1282.1		0.0
Topsoil		0.5
Gravel, silty w/sand Approx. 35% gravel, 40% sand, 30% non plastic fines Brown; saturated; rapid permeability; medium to dense (b=60 to 34); alluvium; OH		0.0
Silt w/sand gravel and sand Approx. 35% gravel, 35% sand, 75% slightly plastic fines, LL=27, PI=6 Gray; moist to wet; slight permeability; v. stiff to hard consistency (b=29 to 38); lacustrine; CL-ML		19.5
Gravel, silty w/sand Approx. 35% gravel, 35% sand, 35% slightly plastic fines, LL=20, PI=6 Gray; moist to wet; slight permeability; v. dense (b=56 to > 100); till; OC-CH		27.0

LABORATORY

TEST HOLE NUMBERING SYSTEM

Test Pit (TP)	Drill Hole (DH)
Centerline of dam	1-00
Barrow Area	101-100
Emergency Spillway	201-200
Centerline of	
Outlet Structure	301-300
Outlet Channel	401-400
Drain Line	501-500
Other	601-600

UNIFIED SOIL CLASSIFICATION SYSTEM (CNS) SYMBOLS

OH Well graded gravel; gravel-sand mixtures  
 OF Poorly graded gravel  
 GS Silty gravel; gravel-sand-silt mixtures  
 GC Clayey gravel; gravel-sand-clay mixtures  
 GV Well graded sand; sand-gravel mixtures  
 SP Poorly graded sand  
 SM Silty sand; sand-silt mixtures  
 SC Clayey sand; sand-clay mixtures  
 ML Silty clay; v. fine sand; sandy or clayey silt  
 CL Clay of low to medium plasticity; silty, sandy or gravelly clay  
 CH Clay of high plasticity; fat clay  
 MH Elastic silt; micaceous or distomaceous silt  
 OL Organic silt and organic silty clay of low plasticity  
 OH Organic clay or silt of medium to high plasticity

II Unified Classification by visual inspection in the field  
 (III) Unified Classification by laboratory analysis

Key to Drill Hole (DH) Logs

Material (LWS)	Depth (ft)
0-21 fpd	0.0
21-26	0.2
26-34	10.4
34-40	14.8

DRY DENSITY

MOISTURE CONTENT

CONPACTION CURVE

FIELD SAMPLE NO 204.1

LABORATORY CLASSIFICATION (CL-ML)

AS BUILT

NEW TOWN: HOFFMAN CREEK  
 WATERSHED PROJECT  
 FLOODWATER CONTROL DAM SITE  
 CHEMUNG COUNTY, NEW YORK  
 LOGS OF TEST HOLE

U. S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE

Logged By: A. Smith  
 Date: 5-18-70  
 Title: 204.1  
 Project: 204.1  
 County: NY-2284-G  
 State: 2284-G



DRAWING 80-778-B42  
 CHECKED BY JF  
 APPROVED BY JHP  
 5-27-81  
 DRAWN BY

# MATERIAL DESCRIPTION

**A**  
 Gravel, silty w/sand; 13-14" max. size, siltstone flags; approx. 4-5% 4-6", 8-10% 3-4", 88-97% matrix (approx. 10-40% gravel, 30-35% sand, 25-30% non plastic fines); brown and gray, saturated, rapid permeability (est.); loose to dense (N=10-34); Alluvium; CM.  
 (D.S. 302.1, CM)

**B**  
 Gravel or sand, silty; 13-14" max. size, subrounded to subangular siltstone w/some flags; approx. 3-5% 4-6", 7-13% 3-4", 79-90% matrix (approx. 30-35% gravel, 25-40% sand, 20-40% none to slightly plastic fines, 44-60, P1-6); gray; moist to unconsolidated; slight to moderate permeability (N=0.00 to 1.37 fyd); medium to very dense (N=24 to >100); till (sometimes unbedded); CC-OM, SC-OM, CM.  
 (D.S. 13-13-14, CC-OM)

**C**  
 Silt, w/gravel and sand; 9-10" max. size, subrounded to subangular siltstone w/some flags; approx. 2-3% 4-6", 4-7% 3-4", 88-90% matrix (approx. 15-20% gravel, 15-20% sand, 30-40% none to slightly plastic fines, 44-60, P1-6); Brown, grayish brown, gray, bluish gray; moist to wet; slight permeability (est.); stiff to hard consistency (N=14 to >100); till; CI-OML.  
 (D.S. 308.1, CC-OM, 310.1, CC-OM; 301.1, CI-OM; 301.2, OM)

**D**  
 Silt, w/gravel and sand; 6-12" max. size, subrounded to subangular siltstone w/some flags; approx. 1-2% 4-6", 2-4% 3-4", 94-97% matrix (approx. 15-20% gravel, 10-20% sand, 30-40% slightly plastic fines, 44-60, P1-6); mottled (gray-brown); moist, slight permeability (est.); medium to hard consistency (N=7 to 84); subcl.; CI-OML.  
 (D.S. 1.1, CI-OML)

**E**  
 Silt, w/some gravel and sand; 2% 3-4", 98% matrix (approx. 8-15% gravel, 10-15% sand, 75-80% slightly plastic fines, 44-60, P1-6); gray; moist to wet; slight permeability (est.); stiff to hard consistency (N=12 to >100); varved, lacustrine; CI-OML.  
 (D.S. 3.1, CI-OML)

**F**  
 Topsoil, dark brown

## BLINDS PIT LOG

SECTION NUMBER 1

TP 21, C.T. Dam, 3/7/70, BAS, 1237.1

0.0 - 0.9 Topsoil - dark brown  
 0.9 - 2.8 Silt, w/sand and gravel  
 6" max. - subrounded to subangular siltstone w/some flags  
 Approx. 15-40%, 25-3-4", 97% matrix (which is approx. 20% gravel, 30% sand, and 40% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subcl.; CI-OML. (D.S. 1.1, CI-OML)

Note: Dry Pit

2.8 - 13.8 Silt, gravelly w/sand  
 14" max. - subrounded to subangular siltstone w/some flags  
 Approx. 25-40%, 45-3-4", 90% matrix (which is approx. 25% gravel, 15% sand, and 60% slightly plastic fines)  
 Brown; moist; slightly permeable; very stiff to hard; homogeneous till; CI-OML

Note: Dry Pit

TP 22, C.T. Dam, 3/9/70, BAS, 1237.4

0.0 - 0.9 Topsoil - dark brown  
 0.9 - 4.8 Silt, w/sand and gravel  
 12" max. - subrounded to subangular siltstone w/some flags  
 Approx. 25-40%, 45-3-4", 90% matrix (which is approx. 25% gravel, 20% sand, and 60% slightly plastic fines)  
 Brown; moist; slightly permeable; very stiff to hard; homogeneous till; CI-OML

4.8 - 13.5 Silt, sandy w/gravel  
 14" max. - subrounded to subangular siltstone w/some flags  
 Approx. 25-40%, 45-3-4", 90% matrix (which is approx. 15% gravel, 20% sand, and 65% slightly plastic fines)  
 Gray; moist; slightly permeable, very stiff to hard; homogeneous till; CI-OML

Note: Moderate seepage @ 9.4'. Caving at completion below 9.4'

TP 23, C.T. Dam, 3/9/70, BAS, 1238.0

0.0 - 1.0 Topsoil - dark brown  
 1.0 - 3.2 Gravel, silty w/sand  
 12" max. - silt flags  
 Approx. 45-40%, 85-3-4", 90% matrix (which is approx. 30% gravel, 35% sand, and 35% non plastic fines)  
 Brown, saturated, rapidly permeable; loose; mixed alluvium; CM

3.2 - 6.2 Silt, w/gravel  
 Approx. 25-3-4", 90% matrix (which is approx. 15% gravel, 10% sand, and 75% slightly plastic fines)  
 Gray, wet, slightly permeable; stiff; homogeneous lacustrine; CI-OML. (D.S. 3.1, CI-OML)

6.2 - 11.0 Gravel, silty w/sand  
 12" max. - silt flags w/some subrounded to subangular cils.  
 Approx. 45-40%, 85-3-4", 90% matrix (which is approx. 15% gravel, 30% sand, and 35% slightly plastic fines)  
 Gray, wet, moderately permeable, dense; homogeneous till; CC-OM

Note: Heavy seepage @ 1.4' and 3.0'

TP 24, C.T. Dam, 3/9/70, BAS, 1238.4

0.0 - 2.0 Silt, w/sand and gravel  
 12" max. - subrounded to subangular silt w/some flags  
 Approx. 25-40%, 45-3-4", 90% matrix (which is approx. 20% gravel, 20% sand, and 60% slightly plastic fines)  
 Grayish brown, moist, slightly permeable; v. stiff; homogeneous till; CI-OML

2.0 - 4.8 Silt  
 Approx. 25-3-4", 90% matrix (which is approx. 15% gravel, 15% sand, and 70% slightly plastic fines)  
 Gray, moist, slightly permeable; v. stiff, homogeneous lacustrine; CI-OML

4.8 - 10.0 Silt, w/sand and gravel  
 16" max. - subrounded to subangular silt w/some flags  
 Approx. 25-40%, 45-3-4", 90% matrix (which is approx. 15% gravel, 20% sand, and 65% slightly plastic fines)  
 Gray, moist, slightly permeable v. stiff, homogeneous till; CI-OML

Note: Light seepage @ 2.0' or upper portion of pit in the slump area

LINE  
NO. 1

subangular siltstone w/some flags  
95% matrix (which is approx. 25% gravel,  
only plastic fines)  
stiff; slightly permeable; v. stiff;  
CL-40. (S.S. 1.1, CL-40)

subangular siltstone w/some flags  
95% matrix (which is approx. 25% gravel,  
only plastic fines)  
stiff; slightly permeable; v. stiff to hard; homogeneous  
till; CL-40.

9.4'. Caving at completion below 9.4'

95% matrix (which is approx. 35% gravel,  
only plastic fines)  
stiff; permeable; loose; mixed alluvium; CL

95% matrix (which is approx. 15% gravel, 10%  
plastic fines)  
stiff; homogeneous lacustrine;  
CL

95% matrix (which is approx. 35% gravel,  
only plastic fines)  
stiff; homogeneous till; CL-40  
CL-40 and 3.0'

95% matrix (which is approx. 20% gravel,  
only plastic fines)  
stiff; homogeneous till; CL-40

95% matrix (which is approx. 5% gravel, 15% sand,  
only plastic fines)  
stiff; homogeneous lacustrine;  
CL

subangular silt w/some flags  
95% matrix (which is approx. 15% gravel,  
only plastic fines)  
stiff; homogeneous till;

95% on upper portion of pit in the

# TP #1. C.T. Box. 5/5/70. BAS. 1314.2

- 0.0 - 0.7 Topsoil - dark brown
- 0.7 - 2.6 Silt, w/sand and gravel  
8" max. - subrounded to subangular silt w/some flags  
Approx. 15% + 6", 35% 3-6", 95% matrix (which is approx. 20% gravel,  
15% sand, and 55% slightly plastic fines)  
Mottled (gray-brown); moist; slightly permeable; stiff; hom-  
ogeneous subsoil; CL-40
- 2.6 - 12.8 Silt, gravelly w/sand  
18" max. - subrounded to subangular silt w/some flags  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx. 25% gravel,  
20% sand, and 55% slightly plastic fines)  
Grayish brown; moist; slightly permeable; v. stiff to hard;  
homogeneous till; CL-40
- 12.8 - 14.9 Silt, sandy w/gravel  
18" max. - subrounded to subangular silt w/some flags  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx. 25% gravel,  
20% sand, and 55% slightly plastic fines)  
Gray; moist; slightly permeable; v. stiff to hard; homogeneous  
till; CL-40

Note: Light seepage @ 1.0'. Some caving at completion.

# TP #101. Borrow Area. 5/5/70. BAS. 1229.2

- 0.0 - 0.9 Topsoil - dark brown
- 0.9 - 2.6 Silt, gravel w/sand  
6" max. - subrounded to subangular silt w/some flags  
Approx. 15% + 6", 35% 3-6", 95% matrix (which is approx. 20% gravel,  
15% sand, and 55% slightly plastic fines)  
Mottled (gray-brown); moist; slightly permeable; stiff; hom-  
ogeneous subsoil; CL-40
- 2.6 - 14.4 Silt, gravel w/sand  
12" max. - subrounded to subangular silt w/some flags  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx. 25% gravel,  
20% sand, and 55% slightly plastic fines)  
Grayish brown; moist; slightly permeable; v. stiff to hard;  
homogeneous till; CL-40
- 14.4 + Silt, sandy w/gravel  
subrounded to subangular silt w/some flags  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx. 20% gravel,  
25% sand, and 55% slightly plastic fines)  
Gray; moist; slightly permeable; v. stiff to hard; homogeneous  
till; CL-40

Note: Dry Pit

# TP #102. Borrow Area. 5/5/70. BAS. 1301.7

- 0.0 - 1.2 Topsoil - dark brown
- 1.2 - 2.6 Silt, gravelly w/sand  
6" max. - subrounded to subangular silt w/some flags  
Approx. 15% + 6", 35% 3-6", 95% matrix (which is approx. 20% gravel,  
15% sand, and 55% slightly plastic fines)  
Mottled (gray-brown); moist; slightly permeable; stiff; hom-  
ogeneous subsoil; CL-40
- 2.6 - 15.0 Silt, gravelly w/sand  
12" max. - subrounded to subangular silt w/some flags  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx. 25% gravel,  
20% sand, and 55% slightly plastic fines)  
Grayish brown; moist; slightly permeable; v. stiff to hard;  
homogeneous till; CL-40
- 15.0 - 16.0 Silt, gravelly w/sand  
8" max. - subrounded to subangular silt w/some flags  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx. 20% gravel,  
25% sand, and 55% slightly plastic fines)  
Bluish gray (coloration due to water table); wet; slightly  
permeable; v. stiff to hard; homogeneous till; CL-40

Note: Light seepage @ 7.0'

# TP #103. Borrow Area. 5/5/70. BAS. 1314.2

- 0.0 - 0.7 Topsoil - dark brown
- 0.7 - 2.9 Silt, gravelly w/sand  
6" max. - subrounded to subangular silt  
Approx. 15% + 6", 35% 3-6", 95% matrix (which is approx. 20% gravel,  
15% sand, and 55% slightly plastic fines)  
Mottled (gray-brown); moist; slightly permeable; stiff;  
homogeneous subsoil; CL-40
- 2.9 - 13.0 Silt, gravelly w/sand  
12" max. - subrounded to subangular silt  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx. 25% gravel,  
20% sand, and 55% slightly plastic fines)  
Grayish brown; moist; slightly permeable; v. stiff to hard;  
homogeneous till; CL-40
- 13.0 - 13.7 Silt, sandy w/gravel  
14" max. - subrounded to subangular silt  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx. 20% gravel,  
25% sand, and 55% slightly plastic fines)  
Gray; moist; slightly permeable; v. stiff to hard; homogeneous  
till; CL-40

Note: Light seepage @ 1.0'

# TP #104. Borrow Area. 5/5/70. BAS. 1204.4

- 0.0 - 1.0 Topsoil, dark brown
- 1.0 - 2.3 Silt, gravelly w/sand  
6" max. - subrounded to subangular silt w/some flags.  
Approx. 15% + 6", 35% 3-6", 95% matrix (which is approx.  
20% gravel, 15% sand, and 55% slightly plastic  
fines)  
Mottled (gray-brown); moist; slightly permeable; stiff;  
homogeneous subsoil; CL-40
- 2.3 - 13.0 Silt, gravelly w/sand  
12" max. - subrounded to subangular silt w/some flags.  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx.  
25% gravel, 20% sand, and 55% slightly plastic  
fines)  
Grayish brown; moist; slightly permeable; v. stiff to  
hard; homogeneous till; CL-40
- 13.0 + Silt, sandy w/gravel  
subrounded to subangular silt w/some flags.  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx.  
20% gravel, 25% sand, and 55% slightly plastic  
fines)  
Gray; moist; slightly permeable; v. stiff to hard;  
homogeneous till; CL-40

Note: Very light seepage at 2.0'.

# TP #105. Borrow Area. 5/5/70. BAS. 1309.3

- 0.0 - 1.0 Topsoil - dark brown
- 1.0 - 4.6 Silt, gravelly w/sand  
12" max. - subrounded to subangular silt w/some flags.  
Approx. 15% + 6", 35% 3-6", 95% matrix (which is approx.  
20% gravel, 15% sand, and 55% slightly plastic  
fines)  
Mottled (gray-brown); moist; slightly permeable; stiff;  
homogeneous subsoil; CL-40
- 4.6 - 14.4 Silt, gravelly w/sand  
14" max. - subrounded to subangular silt w/some flags.  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx.  
25% gravel, 20% sand, and 55% slightly plastic  
fines)  
Grayish brown; moist; slightly permeable; v. stiff to  
hard; homogeneous till; CL-40
- 14.4 - 13.2 Silt, sandy w/gravel  
8" max. - subrounded to subangular silt w/some flags.  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx.  
20% gravel, 25% sand, and 55% slightly plastic  
fines)  
Gray; moist; slightly permeable; v. stiff to hard;  
homogeneous till; CL-40

Note: Light seepage at 7.5' and 2.4'.

# TP #106. Bor. Sect. 5/5/70. BAS. 1311.9

- 0.0 - 1.2 Topsoil - dark brown
- 1.2 - 4.0 Silt, w/sand and gravel  
12" max. - subrounded to subangular silt w/some shale  
Approx. 15% + 6", 35% 3-6", 95% matrix (which is approx.  
20% gravel, 20% sand, and 55% slightly plastic fines)  
Mottled (gray-brown); moist; slightly permeable; stiff;  
homogeneous subsoil; CL-40
- 4.0 - 14.0 Silt, sandy w/gravel  
14" max. subrounded to subangular silt w/some shale  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx.  
20% gravel, 25% sand, and 55% slightly plastic fines)  
Grayish brown; moist; slightly permeable; v. stiff to  
hard; homogeneous till; CL-40
- 14.0 - 15.5 Silt, sandy w/gravel  
10" max. - subrounded to subangular silt w/some shale  
Approx. 25% + 6", 45% 3-6", 95% matrix (which is approx.  
20% gravel, 25% sand, and 55% slightly plastic fines)  
Gray; moist; slightly permeable; v. stiff to hard;  
homogeneous till; CL-40

Note: Very light seepage at 7.2'.

AS BUILT

1-28-76

<p>NEWTOWN-HOFFMAN CREEKS WATERSHED PROJECT FLOODWATER RETARDING DAM SITE 1 CHEMUNG COUNTY, NEW YORK LOGS OF TEST HOLES</p>	
<p>U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE</p>	
<p>Project <u>Basin A. Section 4-76</u></p>	<p>Date <u>5-7-76</u></p>
<p>Drawn <u>.....</u></p>	<p>By <u>.....</u> STATE CONS. ENGINEER</p>
<p>Typed <u>.....</u></p>	<p>File No. <u>NY-2284</u></p>
<p>Checked <u>.....</u></p>	<p>.....</p>

PLATE 7

D'APPOLONIA

DRAWING 80-778-B43  
 7/24/80  
 NUMBER 80-778-B43  
 G. J. G. CHECKED BY JHE  
 5-27-81 APPROVED BY JHP  
 DRAWN BY

**TP #200, Emer. Spwr. 5/4/70, BAS. 1330.0**

- 0.0 - 1.4 Topsoil - dark brown
- 1.4 - 4.0 Silt, w/sand and gravel  
 10" max. - subrounded to subangular silt w/some shale  
 Approx. 15% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 20% sand, and 60% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subsoil; CL-MH
- 4.0 - 14.6 Silt, sandy w/gravel  
 14" max. - subrounded to subangular silt w/some shale  
 Approx. 35% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 25% sand, and 55% slightly plastic fines)  
 Grayish brown; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH

Note: Very light seepage at bottom of pit.

**TP #203, Emer. Spwr. 5/4/70, BAS. 1340.0**

- 0.0 - 1.5 Topsoil - dark brown
- 1.5 - 4.0 Silt, w/sand and gravel  
 8" max. - subrounded to subangular silt w/some shale  
 Approx. 15% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 20% sand, and 60% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subsoil; CL-MH
- 4.0 - 13.0 Silt, sandy w/gravel  
 14" max. - subrounded to subangular silt w/some shale  
 Approx. 35% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 25% sand, and 55% slightly plastic fines)  
 Grayish brown; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH

- 13.0 - 16.6 Silt, sandy w/gravel  
 12" max. - subrounded to subangular silt w/some shale  
 Approx. 35% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 30% sand, and 50% slightly plastic fines)  
 Gray; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH

Note: Light seepage at 3.0'

**TP #214, Emer. Spwr. 5/4/70, BAS. 1345.7**

- 0.0 - 0.9 Topsoil - dark brown
- 0.9 - 2.6 Silt, w/sand and gravel  
 8" max. - subrounded to subangular silt w/some shale  
 Approx. 15% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 20% sand, and 60% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subsoil; CL-MH
- 2.6 - 11.0 Silt, sandy w/gravel  
 14" max. - subrounded to subangular silt w/some shale  
 Approx. 35% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 25% sand, and 55% slightly plastic fines)  
 Grayish brown; moist; slightly permeable; v. stiff to hard (extremely dense at bottom w/boulders); homogeneous till; CL-MH

Note: Light seepage at 1.0' near interface of topsoil and subsoil.

**TP #205, Emer. Spwr. 5/4/70, BAS. 1346.0**

- 0.0 - 1.0 Topsoil - dark brown
- 1.0 - 2.8 Silt, w/sand and gravel  
 8" max. - subrounded to subangular silt w/some shale  
 Approx. 15% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 20% sand, and 60% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subsoil; CL-MH
- 2.8 - 13.4 Silt, w/gravel and sand  
 14" max. - subrounded to subangular silt w/some shale  
 Approx. 35% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 25% sand, and 55% slightly plastic fines)  
 Grayish brown; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH

- 13.4 - 14.4 Silt, sandy w/gravel  
 8" max. - subrounded to subangular silt w/some shale  
 Approx. 25% +, 45% 3-6", 90% matrix (which is approx. 20% gravel, 30% sand, and 50% slightly plastic fines)  
 Gray; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH. D.S. 203.1 (OC-QH)

Note: Light seepage at 1.6' to 9.0'

**TP #207, Emer. Spwr. 5/4/70, BAS. 1350.0**

- 0.0 - 1.0 Topsoil - dark brown
- 1.0 - 2.5 Silt, w/sand and gravel  
 8" max. - subrounded to subangular silt w/some shale  
 Approx. 15% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 20% sand, and 60% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subsoil; CL-MH
- 2.5 - 14.5 Silt, sandy w/gravel  
 12" max. - subrounded to subangular silt w/some shale  
 Approx. 35% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 25% sand, and 55% slightly plastic fines)  
 Grayish brown; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH

Note: Light seepage at 7.0'

**TP #207, Emer. Spwr. 5/4/70, BAS. 1360.0**

- 0.0 - 0.9 Topsoil - dark brown
- 0.9 - 3.3 Silt, w/sand and gravel  
 8" max. - subangular to subrounded silt w/some shale  
 Approx. 15% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 20% sand, and 60% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subsoil; CL-MH
- 3.3 - 15.5 Silt, w/gravel and sand  
 14" max. - subangular to subrounded silt w/some shale  
 Approx. 35% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 25% sand, and 55% slightly plastic fines)  
 Grayish brown; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH

Note: Light seepage at 1.2'

**TP #208, Emer. Spwr. 5/4/70, BAS. 1372.0**

- 0.0 - 0.9 Topsoil - dark brown
- 0.9 - 2.5 Silt, w/sand and gravel  
 8" max. - subrounded to subangular silt w/some shale  
 Approx. 15% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 20% sand, and 60% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subsoil; CL-MH
- 2.5 - 15.0 Silt, sandy w/gravel  
 14" max. - subrounded to subangular silt w/some shale  
 Approx. 35% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 25% sand, and 55% slightly plastic fines)  
 Grayish brown; moist to wet @ 8.3'; slightly permeable; v. stiff to hard; homogeneous till; CL-MH

Note: Light seepage at 8.3' and 0.9'

**TP #209, Emer. Spwr. 5/4/70, BAS. 1377.0**

- 0.0 - 1.4 Topsoil - dark brown
- 1.4 - 3.0 Silt, w/gravel and sand  
 8" max. - subangular and subrounded silt w/some flags  
 Approx. 15% +, 35% 3-6", 90% matrix (which is approx. 20% gravel, 15% sand, and 65% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subsoil; CL-MH
- 3.0 - 14.8 Silt, w/gravel and sand  
 14" max. - subangular and subrounded silt w/some flags  
 Approx. 25% +, 45% 3-6", 90% matrix (which is approx. 25% gravel, 20% sand, and 55% slightly plastic fines)  
 Grayish brown; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH

- 14.8 + Silt, sandy w/gravel  
 14" max. - subrounded to subangular silt w/some flags  
 Approx. 25% +, 45% 3-6", 90% matrix (which is approx. 20% gravel, 25% sand, and 55% slightly plastic fines)  
 Gray; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH

Note: V. light seepage at 6.8'

**TP #210, Emer. Spwr. 5/4/70, BAS. 1380.0**

- 0.0 - 1.6 Topsoil - dark brown
- 1.6 - 3.4 Silt w/sand and gravel  
 8" max. - subrounded to subangular silt w/some shale  
 Approx. 15% +, 35% 3-6", 90% matrix (which is approx. 15% gravel, 15% sand, and 70% slightly plastic fines)  
 Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous subsoil; CL-MH
- 3.4 - 14.3 Silt, gravelly w/sand  
 14" max. - subrounded to subangular silt w/some flags  
 Approx. 25% +, 45% 3-6", 90% matrix (which is approx. 25% gravel, 20% sand, and 55% slightly plastic fines)  
 Grayish brown; moist; slightly permeable; v. stiff to hard; homogeneous till; CL-MH. D.S. 210.1 (OC-QH)

Note: Very light seepage at 3.4'

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff; homogeneous

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff to hard;

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff; homogeneous

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff to hard;

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff; homogeneous

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff; homogeneous

0.9'

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff; homogeneous

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff to hard; homogeneous

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff to hard; homogeneous

slat w some shale  
in (which is approx. 15% gravel,  
the fines)  
stiff; homogeneous

slat w some shale  
in (which is approx. 20% gravel,  
the fines)  
stiff to hard; homogeneous

#### TP #201, Bear. 5/6/70, BAS, 1293.3

- 0.0 - 0.9 Topsoil - dark brown
- 0.9 - 3.2 Silt, gravelly w/sand  
12" max. - subrounded to subangular slat w/some shale  
Approx. 15% +, 35% 3-6", 50% matrix (which is approx. 20% gravel,  
10% sand, and 70% slightly plastic fines)  
Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous  
subsoil; CI-ML
- 3.2 - 14.0 Silt, sandy w/gravel  
12" max. - subrounded to subangular slat w/some shale  
Approx. 25% +, 45% 3-6", 90% matrix (which is approx. 20% gravel,  
25% sand, and 55% slightly plastic fines)  
Grayish brown; moist; slightly permeable; v. stiff to hard;  
homogeneous till; CI-ML
- Note: Light seepage at 2.2'

#### TP #401, Bear. 5/6/70, BAS, 1293.4

- 0.0 - 0.8 Topsoil - dark brown
- 0.8 - 2.2 Gravel, silty w/sand  
12" max. - slat flags  
Approx. 35% +, 15% 3-6", 85% matrix (which is approx. 40% gravel,  
35% sand, and 25% non-plastic fines)  
Brown; saturated; rapidly permeable; loose; homogeneous alluvium;  
CI
- 2.2 - 6.5 Gravel, silty w/sand  
16" max. - slat flags w/some subrounded to subangular chls.  
Approx. 35% +, 15% 3-6", 75% matrix (which is approx. 40% gravel,  
35% sand, and 25% non-plastic fines)  
Gray; saturated; rapidly permeable; loose; homogeneous alluvium;  
CI
- 6.5 - 12.0 Gravel, silty w/sand  
14" max. - subrounded to subangular slat w/some flags  
Approx. 35% +, 15% 3-6", 85% matrix (which is approx. 35% gravel,  
25% sand, and 40% non-plastic fines)  
Gray; wet; moderately permeable; dense; homogeneous till; CI
- Note: Heavy seepage at 2.2'

#### TP #501, Drain Line, 5/6/70, BAS, 1293.4

- 0.0 - 0.8 Topsoil - dark brown
- 0.8 - 2.0 Silt, w/sand and gravel  
14" max. - subrounded to subangular slat w/some flags  
Approx. 25% +, 25% 3-6", 95% matrix (which is approx. 20% gravel,  
10% sand, and 70% slightly plastic fines)  
Mottled (gray-brown); moist; slightly permeable; stiff; homogeneous  
subsoil CI-ML
- 2.0 - 9.0 Silt, gravelly w/sand  
12" max. - subrounded to subangular slat w/some flags  
Approx. 25% +, 25% 3-6", 95% matrix (which is approx. 15% gravel,  
15% sand, and 70% slightly plastic fines)  
Brown; moist; slightly permeable; v. stiff to hard; homogeneous;  
till; CI-ML. D.S. 501.1 (CI-ML)
- 9.0 - 12.5 Silt, gravelly w/sand  
14" max. - subrounded to subangular slat w/some flags  
Approx. 25% +, 25% 3-6", 95% matrix (which is approx. 20% gravel,  
15% sand, and 65% slightly plastic fines)  
Gray; moist; slightly permeable; v. stiff to hard; homogeneous till;  
CI-ML. D.S. 501.2 (CI-ML)
- Note: Dry pit.

#### TP #601, Drain Line, 5/6/70, BAS, 1293.9

- 0.0 - 1.0 Topsoil - dark brown
- 1.0 - 4.5 Gravel, silty w/sand  
14" max. - slat flags  
Approx. 35% +, 15% 3-6", 85% matrix (which is approx. 40% gravel,  
35% sand, and 25% non-plastic fines)  
Brown; saturated; rapidly permeable; loose; homogeneous alluvium;  
CI. D.S. 502.1 (CI)
- 4.5 - 10.0 Sand, silty w/gravel  
14" max. - slat flags w/subround to subangular chls.  
Approx. 45% +, 15% 3-6", 75% matrix (which is approx. 35% gravel,  
45% sand, and 20% non-plastic fines)  
Gray; saturated; rapidly permeable; loose; homogeneous till (washed)  
CI
- 10.0 - 11.0 Silt, w/sand and gravel  
12" max. - slat flags w/subround to subangular chls.  
Approx. 35% +, 15% 3-6", 85% matrix (which is approx. 20% gravel,  
20% sand, and 60% slightly plastic fines)  
Gray; wet; slightly permeable; dense; homogeneous till; CI-ML
- Note: Heavy seepage at 1.0'

#### TP #101, Drain Line, 5/6/70, BAS, 1297.2

- 0.0 - 2.0 Topsoil - dark brown, including subsoil
- 2.0 - 5.5 Silt, gravelly w/sand  
14" max. - subround to subangular slat w/some flags  
Approx. 25% +, 45% 3-6", 90% matrix (which is approx.  
25% gravel, 20% sand, and 55% slightly plastic fines)  
Mottled (gray-brown); moist; slightly permeable; v. stiff;  
homogeneous till; CI-ML
- 5.5 - 14.0 Silt, gravelly w/sand  
18" max. - subround to subangular slat w/some flags  
Approx. 35% +, 35% 3-6", 95% matrix (which is approx.  
25% gravel, 15% sand, and 60% slightly plastic fines)  
Gray; moist; slightly permeable; v. stiff; homogeneous  
till; CI-ML
- Note: Light seepage at 5.3'

#### TP #201, Other, 5/6/70, BAS, 1298.4

- 0.0 - 1.4 Topsoil - dark brown
- 1.4 - 5.3 Silt, gravelly w/sand  
18" max. - subrounded to subangular slat w/some flags  
Approx. 35% +, 35% 3-6", 95% matrix (which is approx. 25%  
gravel, 10% sand, and 65% slightly plastic fines)  
Brown; moist; slightly permeable; v. stiff; homogeneous  
till; CI-ML
- 5.3 - 12.5 Sand, silty w/gravel  
14" max. - subrounded to subangular slat w/some flags  
Approx. 35% +, 15% 3-6", 85% matrix (which is approx. 30%  
gravel, 35% sand, and 35% slightly plastic fines)  
Gray; v. wet; moderately permeable; loose; homogeneous  
till (washed); SC-SH
- 12.5 - 14.0 Silt, sandy w/gravel  
12" max. - subrounded to subangular slat w/some flags  
Approx. 25% +, 45% 3-6", 90% matrix (which is approx. 15%  
gravel, 20% sand, and 65% slightly plastic fines)  
Gray; wet; slightly permeable; v. stiff; homogeneous  
till; CI-ML
- Note: Moderate seepage @ 6.4' - Caved at completion.

#### TP #301, Other, 5/6/70, BAS, 1298.4

- 0.0 - 1.2 Topsoil - dark brown
- 1.2 - 3.5 Silt, w/sand and gravel  
14" max. - subround to subangular slat w/some flags  
Approx. 25% +, 45% 3-6", 90% matrix (which is approx. 20%  
gravel, 20% sand, and 60% slightly plastic fines)  
Grayish brown; moist; slightly permeable; v. stiff;  
homogeneous till; CI-ML
- 3.5 - 8.8 Silt  
Approx. 25% 3-6", 90% matrix (which is approx. 15% gravel,  
15% sand, and 70% slightly plastic fines)  
Gray; moist; slightly permeable; v. stiff; homogeneous  
lacustrine; CI-ML
- 8.8 - 13.0 Silt, w/sand and gravel  
12" max. - subround to subangular slat w/some flags  
Approx. 25% +, 45% 3-6", 90% matrix (which is approx. 15%  
gravel, 20% sand, and 65% slightly plastic fines)  
Grayish brown; moist; slightly permeable; v. stiff;  
homogeneous till; CI-ML
- Note: Dry pit.

AS BUILT

1-28-76

NEWTOWN-HOFFMAN CREEKS  
WATERSHED PROJECT  
FLOODWATER RETARDING DAM SITE I  
CHEMUNG COUNTY, NEW YORK  
LOGS OF TEST HOLES

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

Logged <i>Burt A. Burt</i>	Date <i>5-28-76</i>	Drawn <i>Richard J. Phillips</i>
Drawn		State Cons. Engineer
Traced		
Checked		



PLATE 8

D'APPOLONIA

APPENDIX F

GEOLOGY MAP

DRAWN BY  
 ACS  
 4-29-81  
 CHECKED BY  
 7-24-81  
 APPROVED BY  
 7-24-81  
 DRAWING 80-778-A4  
 NUMBER 7-24-81



GEOLOGY MAP

REFERENCE  
 GEOLOGIC MAP OF NEW YORK, FINGER LAKES SHEET  
 DATED 1970 SCALE 1:250,000

**DAPPOLONIA**

DRAWN BY  
 ACS  
 4-29-81  
 CHECKED BY  
 3E  
 5/7/81  
 APPROVED BY  
 4P  
 5-7-81  
 DRAWING NUMBER  
 80-778-A6

## LEGEND

### CANADAWAY GROUP

800-1200 ft. (240-370 m.)

Dcy Machias Formation—shale, siltstone; Rushford Sandstone; Caneadea, Canisteo, and Hume Shales; Canaseraga Sandstone; South Wales and Dunkirk Shales; In Pennsylvania: Towanda Formation—shale, sandstone.

### JAVA GROUP

300-700 ft. (90-210 m.)

Dj Wiscay Formation—sandstone, shale; Hanover and Pipe Creek Shales

### WEST FALLS GROUP

1100-1600 ft. (340-490 m.)

Dwn Nunda Formation—sandstone, shale.  
 Dwrg West Hill and Gardeau Formations—shale, siltstone; Roricks Glen Shale; upper Beers Hill Shale; Grimes Siltstone.  
 Dwr lower Beers Hill Shale; Dunn Hill, Millport, and Moreland Shales.  
 Dwc Nunda Formation—sandstone, shale; West Hill Formation—shale, siltstone; Corning Shale.  
 Dwnm "New Milford" Formation—sandstone, shale.  
 Dwrg Gardeau Formation—shale, siltstone; Roricks Glen Shale.  
 Dwr Slide Mountain Formation—sandstone, shale, conglomerate.  
 Dwnm Beers Hill Shale; Grimes Siltstone; Dunn Hill, Millport, and Moreland Shales

### SONYEA GROUP

200-1000 ft. (60-300 m.)

Ds In west: Cashaqua and Middlesex Shales.  
 In east: Rye Point Shale, Rock Stream ("Enfield") Siltstone; Pulteney, Sawmill Creek, Johns Creek, and Montour Shales.

### GENESEE GROUP AND TULLY LIMESTONE

200-1000 ft. (60-300 m.)

Dg West River Shale; Genundewa Limestone; Penn Yan and Genesee Shales; all except Genesee replaced eastwardly by Ithaca Formation—shale, siltstone and Sherburne Siltstone.  
 Dgo Oneonta Formation—shale, sandstone  
 Dgt Unadilla Formation—shale, siltstone.  
 Dt Tully Limestone.

### LOCKPORT GROUP

80-175 ft. (25-55 m.)

Sl Oak Orchard and Penfield Dolostones, both replaced eastwardly by Sconondoa Formation—limestone, dolostone.

GEOLOGY MAP LEGEND

#### REFERENCE

GEOLOGIC MAP OF NEW YORK, FINGER LAKES SHEET  
 DATED 1970, SCALE 1"=250,000

**D'APOLONIA**

APPENDIX G  
STABILITY ANALYSES



UNITED STATES DEPARTMENT OF AGRICULTURE

SOIL CONSERVATION SERVICE - Soil Mechanics Laboratory

XXXXXXXXXXXXXXXXXXXX 800 "J" Street, Lincoln, Nebraska 68508

SUBJECT: ENG 22-5, New York WP-08, Newton-Hoffman, Site #1      DATE: February 4, 1971  
(Chemung County)

TO: Richard L. Phillips, State Conservation Engineer,  
SCS, Syracuse, New York

ATTACHMENTS

1. Form SCS-354, Soil Mechanics Laboratory Data, 1 sheet.
2. Form SCS-355A, Triaxial Shear Test Data, 2 sheets.
3. Form SCS-352, Compaction and Penetration Resistance, 1 sheet.
4. Form SCS-357, Summary - Slope Stability Analysis, 2 sheets.
5. Figure No. 1, Compactive Effort vs. Compacted Density, 1 sheet.
6. Investigational Plans and Profiles.

DISCUSSION

GENERAL.

The proposed 54-foot high damage class c flood control dam is located in the Allegheny Plateau physiographic area of Chemung County. The foundation material is principally glacial till with some lacustrine material in the floodplain section.

FOUNDATION.

- A. Soil Classification. Foundation samples were not submitted to the Soil Mechanics Laboratory for testing. The field classification, along with gradation and plasticity data obtained in the field laboratory, are included in the geology report.

EMBANKMENT.

- A. Soil Classification. One sample of glacial till was submitted from the borrow area. The sample contains 33 percent gravel size material and 52 percent fines. The LL is 25 and the PI is 6. It is classed as a CL-ML.

A dispersion test indicated 32 percent dispersion in the fraction finer than 0.005 mm.

Subj: ENG 22-5, New York WP-08, Newton-Hoffman Site #1

- B. Compacted Density. A Standard Proctor compaction test was made on the minus No. 4 fraction. The maximum dry density obtained was 120.5 pcf and the optimum moisture content is 12 percent.

In addition to the Standard Proctor test, tests were made at varying compactive efforts, and the data obtained are shown on the attached Figure No. 1.

- C. Shear Strength. The till submitted from Site 3A on this watershed appear to be comparable to the till at this site. Consolidated undrained tri-axial shear tests were made on the till from Site 3A at 95 percent of Proctor density and low shear strength parameters were obtained. It appeared that a higher test density was necessary, and the sample from this site was tested at 97 percent of Proctor density. Low shear strength parameters were obtained at this density also, and additional tests were made on the Site 3A samples of till at 100 percent of Proctor density. The shear test data obtained on the samples from Site 3A and the sample from this site are summarized as follows:

Site No.	Sample No.	% < No. 4	LL	PI	Class	Test Density		B Parameter	Shear Strength Parameters			
						γ <sub>d</sub> pcf	% Proctor		Total Stress		Effective Stress	
									φ deg	c psf	φ̄ deg	c̄ psf
1	204.1	67	25	6	CL-ML	116.8-118.5	97-98.5	0.97-0.98	18½	0	26½	0
3A	207.1	89	19	2	ML	114.9-115.7	95-95.5	0.96-1.0	19	0	26½	0
						118.7-119.4	98-98.7	0.95-0.96	21	575	32	0
3A	108.1	70	29	9	CL	111.0-111.2	94.5	0.96-0.99	12	175	22½	125
						116.7-118.2	100	0.98-1.0	15	425	25	200

The data indicates that these materials have low shear strength at 95 percent of Proctor density. The compaction study shown on Figure No. 1 indicates that 95 percent of Proctor density is obtained with a compactive effort of about 5000 ft.lbs. per cubic foot, which is in the range of 40 percent of Standard Proctor compactive effort.

The low shear strength parameters obtained at 95 percent of Proctor density may result because of the relatively small amount of energy applied to obtain this density. The laboratory data indicate that this type of material should compact quite well on the fill and that a density in the range of 100 percent of Proctor is necessary.

Subj: ENG 22-5, New York WP-08, Newton-Hoffman Site #1

On the basis of the testing from this site and from Site 3A, we suggest that the shear strength parameters obtained on the till at 100 percent of Proctor density from Site 3A be used for this site also.

#### SLOPE STABILITY.

The stability of the proposed 3:1 upstream slope and the  $2\frac{1}{2}$ :1 downstream slope was checked with a Swedish circle method of analyses and with a block method of analyses. The circle analyses considered the embankment only and it was made with the computer and the SCS program. The NavDocks block method was used and it considered the embankment and 2 feet of  $\phi = 35^\circ$ ,  $c = 0$  foundation material. The upstream slope was analyzed for the full drawdown condition and the downstream slope was analyzed for the full drawdown condition with a drain at the  $c/b = 0.6$  point.

The circle analyses for the 3:1 upstream slope with planned 10-foot berm, using total stress shear strength parameters of  $\phi = 15^\circ$ ,  $c = 425$  psf, shows a factor of safety of 1.36. The block analyses, considering the foundation, shows a factor of safety of 1.59. The circle analyses on the downstream slope shows that a 20-foot berm is required at elevation 1300 in order to obtain an acceptable factor of safety (Trial 5A,  $F_s = 1.52$ ).

An infinite slope analysis was made for the upstream slope of Site 3A considering the effective stress shear strength parameters of  $\phi = 32^\circ$ ,  $c = 0$ . For the condition of parallel flow, a 3:1 slope has a factor of safety of 1.02 and a  $3\frac{1}{2}$ :1 slope has a factor of safety of 1.19. For the condition of horizontal flow, a 3:1 slope has a factor of safety of 0.93 and a  $3\frac{1}{2}$ :1 slope has a factor of safety of 1.12.

#### CONCLUSIONS AND RECOMMENDATIONS

- A. Site Preparation. The material designated as F in the floodplain and described as floodplain silt and topsoil was not tested for strength; therefore, we suggest that it be stripped from the foundation area of the dam.

The material designated as slump on the lower part of the left abutment should be removed from the base area of the dam and we concur with the proposal to excavate the slope to 2:1.

- B. Cutoff. We concur with the proposal to bottom the cutoff trench in the till and the lacustrine material underlying the GM alluvium which is designated as material A. On the abutments, the trench should bottom in till below the zone affected by surface disturbances. A minimum trench depth of 4 feet is suggested.

We suggest that the trench backfill be compacted to 100 percent of Proctor density.

Richard L. Phillips

Subj: ENG 22-5, New York WP-08, Newton-Hoffman Site #1

4

- C. Principal Spillway. It is reported that no unusual problems are expected.
- D. Drain. We recommend that a foundation trench drain be used to provide a controlled outlet for seepage that may be expected to by-pass the cutoff. We suggest that the drain be located at about the  $c/b = 0.6$  point, and we suggest that it be carried up the abutments to about elevation 1305. In the floodplain, the trench should extend through the GM alluvium designated as material A and we suggest that it penetrate the till on the abutments to at least a 4-foot depth.


When the cutoff trench is opened, the conditions on the left abutment should be evaluated to determine if additional drainage measures are required.

The filter requirements should be checked in order to meet the criteria outlined in Soil Mechanics Note No. 1.

E. Embankment Design.

1. Placement of Materials. We recommend that the till used for the embankment be placed at a minimum of 100 percent of Standard Proctor density. The placement moisture content should be near optimum.
2. Slopes. The following slopes are suggested:
  - a. Upstream:  $3\frac{1}{2}:1$  in the area where the slope will be subjected to drawdown. A steeper slope can be used above this point. The test data indicate that the shear strength parameters are quite sensitive to changes in density and, since it appears possible that the effective  $\bar{c}$  parameter might be 0, we are suggesting the flatter slope to reduce the possibility of shallow slides developing during drawdown. Your experience with these materials may indicate that a 3:1 slope would be satisfactory, however.
  - b. Downstream.  $2\frac{1}{2}:1$  with a 20-foot berm at elevation 1300.
3. Settlement. An overfill allowance of 0.75-foot is suggested to compensate for residual consolidation.

Prepared by:

  
Lorn P. Dunnigan, Head  
Soil Mechanics Laboratory


Attachments

cc: Bernard S. Ellis, Syracuse, N.Y.  
Loring C. Ibbitson, Syracuse, N.Y.  
D. W. Shanklin, Binghamton, N.Y.  
Neil F. Bogner, Upper Darby EWP

<b>MATERIALS TESTING REPORT</b>	U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	<b>TRIAxIAL SHEAR TEST</b> with pore pressure measured
-------------------------------------	---	---

PROJECT and STATE <i>NEWTON GREENWICH SITE: 1 NEW YORK</i>		SAMPLE LOCATION <i>ENCL. 2 P. 11 MATERIAL C</i>	
TYPE OF SAMPLE <i>COLLECTED</i>	TESTED AT <i>SAINT LUCAS</i>	APPROVED BY	DATE

MINOR PRINCIPAL STRESS, $\sigma_3$ (psi)	PORE PRESSURE, $u$ (psi)	EFFECTIVE MINOR PRINCIPAL STRESS, $\bar{\sigma}_3$ (psi)	DEVIATOR STRESS, $\sigma_1 - \sigma_3$ (psi)	FAILURE CRITERIA	AXIAL STRAIN AT FAILURE, $\epsilon$ (%)
<i>10</i>	<i>3.0</i>	<i>7.0</i>	<i>9.3</i>		<i>3.0</i>
<i>20</i>	<i>8.4</i>	<i>11.6</i>	<i>16.7</i>		<i>6.1</i>
<i>30</i>	<i>11.2</i>	<i>18.8</i>	<i>33.1</i>		<i>7.0</i>




REMARKS *BACKPRESSURED*

*R. H. G.*

<b>MATERIALS TESTING REPORT</b>		U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE		<b>TRIAXIAL SHEAR TEST</b>					
PROJECT and STATE <u>NEBRASKA - 1165000000 SITE: 1</u>			SAMPLE LOCATION <u>END. SP. 11. MATCOILL C</u>						
FIELD SAMPLE NO. <u>394.1</u>		DEPTH <u>2.6 - 11.0</u>		GEOLOGIC ORIGIN					
TYPE OF SAMPLE <u>COMPACTED</u>		TESTED AT <u>SNL - LINCOLN</u>		APPROVED BY DATE					
INDEX TEST DATA			SPECIMEN DATA		TYPE OF TEST				
USCS <u>CL-NIL</u> ; LL <u>25</u> ; PI <u>6</u>			HEIGHT <u>3.0</u> "; DIAMETER <u>1.4</u> "		UU <input type="checkbox"/> Q CU <input type="checkbox"/> R CU <input checked="" type="checkbox"/> S CD <input type="checkbox"/> S				
% FINER (mm): 0.002 <u>10</u> ; 0.005 <u>16</u> ; 0.074 (# 200) <u>52</u>			MATERIALS TESTED PASSED <u>#4</u> SIEVE						
G <sub>s</sub> (-#4) <u>2.75</u> ; G <sub>s</sub> (+#4)			METHOD OF PREPARATION <u>HANDS</u>						
STANDARD: Y <sub>d</sub> MAX. <u>120.5</u> pcf; w <sub>o</sub> <u>10.5</u> %			MOLDING MOISTURE <u>13.0</u> %						
MODIFIED: Y <sub>d</sub> MAX. _____ pcf; w <sub>o</sub> _____%			MOLDED AT <u>77.2</u> % OF Y <sub>d</sub> MAXIMUM						
DRY DENSITY		5 REMARKS	MOISTURE CONTENT, %			TIME OF CONSOLIDATION (hrs)	MINOR PRINCIPAL STRESS $\sigma_3$ (psi)	DEVIATOR STRESS $\sigma_1 - \sigma_3$ (psi)	AXIAL STRAIN AT FAILURE, $\epsilon$ (%)
INITIAL pcf <input type="checkbox"/> g/cc <input type="checkbox"/>	CONSOLIDATED pcf <input type="checkbox"/> g/cc <input type="checkbox"/>		START OF TEST	DEG. OF SAT. AT START OF TEST	END OF TEST				
<u>115.5</u>	<u>117.6</u>		<u>0.93</u>		<u>13.1</u>				
<u>117.6</u>	<u>118.5</u>		<u>0.78</u>		<u>13.0</u>				
<u>118.5</u>			<u>0.77</u>		<u>12.9</u>				
DEVIATOR STRESS ( $\sigma_1 - \sigma_3$ ), psi									
<div style="border: 1px solid black; padding: 5px; width: fit-content; margin: 10px auto;"> <b>SHEAR PARAMETERS</b>  <math>\phi</math> <u>13.5</u> deg.  <math>\tan \phi</math> <u>.335</u>  <math>c</math> <u>0</u> psf       </div>									
NORMAL STRESS ( $\sigma$ ), psi									
REMARKS <u>BACKCALCULATED</u>									

MATERIALS TESTING REPORT		U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE		CORRELATION AND PENETRATION RESISTANCE	
PROJECT AND STATE <u>Newtown Hoffman #1</u> <u>NEW YORK</u>					
FIELD SAMPLE NO. <u>204.1</u>		LOCATION <u>Em. Spwy Material C</u>			DEPTH <u>2.6' - 11'</u>
GEOLOGIC ORIGIN		TESTED AT <u>SML-LINCOLN</u>		APPROVED BY	DATE
CLASSIFICATION <u>CL-MC</u> LL <u>35</u> PI <u>6</u>		CURVE NO. <u>1</u> OF <u>1</u>			
MAX. PARTICLE SIZE INCLUDED IN TEST <u>#4</u>		STD. (ASTM D-698) <input checked="" type="checkbox"/> METHOD <u>A</u>			
SPECIFIC GRAVITY (G <sub>s</sub> ) { MINUS NO. 4 <u>2.73</u> PLUS NO. 4 <u>2.73</u>		MOD. (ASTM D-1557) <input type="checkbox"/> METHOD <u>1</u>			
OTHER TEST <input type="checkbox"/> (SEE REMARKS)					



REMARKS

CURVE IS FOR THE MINUS NO. 4 FRACTION  
GRADATION OF TOTAL SAMPLE  
< NO. 200 52%; < NO. 4 67%; < 3" 100%

MATERIALS TESTING REPORT		U. S. DEPARTMENT of AGRICULTURE SOIL CONSERVATION SERVICE		SUMMARY - SLOPE STABILITY ANALYSIS		
PROJECT and STATE NEWTON HOFFMAN SITE #1 NEW YORK				DATE 2-1-71		
METHOD OF ANALYSIS SWEDISH CIRCLE & BLOCK				ANALYZED AT S.M.L. LINCOLN, IL		
APPROVED BY						
SOURCE AND USE OF MATERIALS	CLASSIFICATION	ADOPTED DESIGN DATA				REMARKS
		$\gamma_d$ (pcf)	$\gamma_{sat}$ (pcf)	$\phi$ (deg)	$c$ (psf)	
① Foundation						Assumed $\gamma_{sat}$ value CU } CU } From CU } Site #3A CU }
② Embankment	ML	119.0	133.2	21	57.5	
③				32	0	
④ Embankment	CL	117.7	135.2	15	42.5	
⑤				25	200	
⑥						
⑦						
⑧						
TRIAL NO.	SLOPE	CONDITIONS @ Station				$F_s$
10/1	3:1	Maximum Section - 10' berm @ elev. 1300.7 - Arc cut thru emb. (15°-42.5) only.				1.39
20/1	3:1	Same conditions as trial #1.				1.36
30/1	3:1	Same conditions as trial #1.				1.30
40/1	2 1/2:1	Drain 3' - 2' - No berm - Arc cut thru emb. (15°-42.5) only.				1.36
50/1	2 1/2:1	Drain 0' - 2' - No berm - Arc cut thru emb. (15°-42.5) only.				1.35
50/2	2 1/2:1	Same conditions as trial #5 except 20' berm @ elev. 1300.7.				1.52
60/1	2 1/2:1	Same conditions as trial #5A.				1.57
70/1	3:1	Block Analysis - Full drawdown - 12' berm @ elev. 1300.7 - Emb. (15°-42.5).				1.50
80/1	3:1	42' found (35°-0).				1.53
90/1	3:1	Block Analysis - No berm - Arc cut thru emb. (15°-42.5) 42' found (35°-0).				








Figure No. 1

## APPENDIX H

### REFERENCES

## APPENDIX H

### REFERENCES

Broughton, J. G., D. W. Fisher, Y. W. Isachsen, and L. V. Rickard, 1966, "Geology of New York," New York State Museum and Science Service, Educational Leaflet 20, 50 pp.

Fisher, D. W., Y. W. Isachsen, and L. V. Rickard, 1971, "Generalized Tectonic-Metamorphic Map of New York," New York Museum and Science Service, Map and Chart Series No. 15.

Flint, R. F., 1971, Glacial and Quaternary Geology, John Wiley and Sons, Inc., 892 pp.

Rickard, L. V. and D. W. Fisher, 1970, "Geologic Map of New York, Finger Lakes Sheet," New York State Museum and Science Service, Map and Chart Series No. 15.

Thornburg, W. D., 1965, Regional Geomorphology of the United States, John Wiley & Sons, Inc., 609 pp.

U.S. Army Corps of Engineers, 1956, Hydrometeorological Report No. 33.

U.S. Department of Commerce, 1965, Weather Bureau Hydrometeorological Report No. 40.

U.S. Department of the Interior, Bureau of Reclamation, 1974, Design of Small Dams.

Wright, H. E., Jr. and D. G. Frey, 1965, The Quaternary of the United States, Princeton University Press, 922 pp.

EN

DAT  
FILM

2-

DTI